

Bryan Ellis

Environmental Affairs Division

TO:

# **MEMORANDUM**

**DATE**: 08/07/12

| FROM:                        | Director of Transportation, Planning, & Development  |
|------------------------------|--|
| SUBJECT:                     | Determination of PCE for US 82<br>CSJ 0046-04-057  |
| The Atlanta District         | has completed a PCE document for the above referenced project. I certify that:   |
|                              | locument supports a determination that the proposed project meets current FHWA   |
| exception for document a     | sed project does not meet current FHWA criteria for a PCE, FHWA has approved ar<br>or this project and written evidence of FHWA approval is attached to the PCE<br>is provided in sections B and E(1) of the Programmatic Agreement for the Review and<br>NEPA Categorically Excluded Transportation Projects. |
| <ol><li>The PCE do</li></ol> | ocument meets all current standards of submission for a PCE project.   |
|                              | ation disclosed in the PCE document is supported by evidence in the District project<br>letion of all studies and coordination needed to verify that the proposed project meets<br>for a PCE.  |
| further certify one          | of the following:  |
|                              | E document has been subjected to QA/QC review by the document preparer and a staff member, and was complete and accurate as of the date it was transmitted to me fication,   |
| OR                           |  |
| District                     | E document has been subjected to QA/QC review by the document preparer. The has performed QA/QC review and has determined that as of the date it was ted to me for certification:  |
| a. The                       | PCE document is complete, AND  |
|                              | PCE document is accurate with respect to areas for which the District has opriately qualified staff, AND   |
|                              | District does not have staff with the expertise to verify that the PCE document is<br>rrate with respect to the following sections:  |
|                              | i  |
|                              | i  |
| iii                          |  |
| iv                           |  |
| V                            |  |
| Vi                           | MM/h/ [2] 2212   |
| Certified by:                | Director of TP&D   |
| Name                         | Title Date   |
|                              |  |

# **PCE Determination Form**

Note: If an issue is "Not Applicable," write "N/A" in the "No" column.

| YES | NO  | Description of Item Sufficiency   |
|-----|-----|---|
| X   |     | There are no more than 30 acres, or 6 acres per linear mile, of new right of way.   |
| Χ   |     | The action shall follow the requirements of the Uniform Relocation Act.   |
| Х   |     | There are no commercial or residential displacements.   |
| х   |     | There are no "use" of properties protected by Section 4(f) of the Department of Transportation Act (as defined in 49 U.S.C. 303). Any de minimis action shall be received, processed and approved, if appropriate by FHWA before a project is allowed to be processed as PCEs.  |
| Х   |     | ENV or SHPO has determined that the project poses "no adverse effects" to properties eligible for or listed in the National Register of Historic Places.  |
| Х   |     | The proposed action is not subject to an individual Section 408, 404 and/or Section 10 permit, or Nationwide Permit 23 issued by the U. S. Army Corps of Engineers.   |
| х   |     | The proposed action is not subject to a Section 9 permit issued by the U.S. Coast Guard (USCG).  Further, any required USCG advanced approval and/or lighting exemption concurrence is/was received before letting.   |
| Х   |     | The action does not lead to any determination other than "no effect" or "may effect, but not likely to adversely affect" for federally listed resources, under regulations implementing the Endangered Species Act. This includes any species and any designated critical habitat.  Essential fish habitat meets the equivalent level of effect as applicable under |
|     |     | the laws and regulations governing that program.  |
| х   |     | The action does not necessitate construction in or adjacent to the specific section of the Rio Grande River designated as a component in the <a href="National System of Wild and Scenic Rivers">National System of Wild and Scenic Rivers</a> .  |
| х   |     | The action does not involve known hazardous materials impacts anticipated to adversely affect construction activities, and does not involve the acquisition of known unresolved contaminated sites where TxDOT could reasonably expect to assume liability for corrective action upon acquisition.  |
|     | N/A | The action is consistent with the Coastal Zone Management Plan as determined by the appropriate federal and/or state agency(ies).   |
| х   |     | The action conforms to all applicable laws, regulations, implementation plans, or other applicable federal and state air quality requirements pursuant to the federal and Texas Clean Air Acts.   |

No significant social, economic, and/or environmental impacts associated with this project have been discovered. Therefore, the proposed action is certified/approved as a Programmatic Categorical Exclusion.

Certified/Approved Date

# **Programmatic Categorical Exclusion**

Reconstruct 2-lane rural roadway to provide passing lanes

US-82 from FM 1840 to SH 98

**Bowie County** 

CSJ 0046-04-057

U.S. Department of Transportation Federal Highway Administration

and

Texas Department of Transportation

September 2012

# **Table of Contents**

| Introduction  | 1   |
|---|-----|
| Proposed Action                                     | 1   |
| Existing Facility                                   |     |
| Planned Facility                                    |     |
| Funding and Planning                                |     |
| Need and Purpose                                    |     |
| Alternatives  |     |
| Bicycle and Pedestrian Accommodations               |     |
| Right of Way and Utility Adjustment                 |     |
| Surrounding Area                                    | 3   |
| Specific Areas of Environmental Concern             | 4   |
| Socioeconomics                                      | 4   |
| Section 4(f) Properties                             | 7   |
| Historic Properties                                 | 8   |
| Archeological Resources                             | 8   |
| Vegetation  | 8   |
| Endangered Species Act                              | 10  |
| Federal and State Threatened and Endangered Species |     |
| State Species of Concern                            |     |
| Water Resources                                     |     |
| Prime, Unique, and Special Farmlands                |     |
| Noise Assessment                                    |     |
| Hazardous Materials                                 |     |
| Wild and Scenic Rivers                              |     |
| Air Analysis  |     |
| Environmental Permits, Issues, and Commitments      | 32  |
| Public Involvement                                  | 34  |
| Conclusion  | 3/1 |

# **List of Tables**

| Table 1: Minority Population Percentages                     | 5  |
|--|----|
| Table 2: Median Household Income and Poverty Level           | 7  |
| Table 3: Federal, State Listed Threatened/Endangered Species | 11 |
| Table 4: Waters of the US and Anticipated Impacts            | 20 |
| Table 5: FHWA Noise Abatement Criteria                       | 23 |
| Table 6: Traffic Noise Levels                                | 25 |

# **Appendices**

Appendix A: General Location Map and Project Topographic Maps

Appendix B: Typical Sections

Appendix C: Photo Log

Appendix D: STIP page

Appendix E: Coordination Documents (Archaeological, Historical, and Texas Parks and

Wildlife Department)

Appendix F: USACE Preliminary Jurisdictional Determination

Appendix G: Traffic Noise Receivers

#### Introduction

This Programmatic Categorical Exclusion (PCE) presents the potential social, economic, and environmental effects that would result from the proposed improvements to US-82 in Bowie County, Texas. Planned improvements include the construction of a passing lane for approximately 8.7 miles from FM 1840 in DeKalb, Texas, to SH 98 near New Boston, Texas. Running parallel and adjacent to the project on the south side is the old Texas and Pacific Railway which has been railbanked in accordance with the National Trails System Act for use as a recreational trail.

Refer to **Appendix A** for the General Location Map and Project Topographic Map. Refer to **Appendix B** for the existing and proposed typical sections. Refer to **Appendix C** for project area photographs.

# **Proposed Action**

## Existing Facility

US-82 is a 2-lane roadway with 8-foot to 10-foot shoulders and an open storm drainage system. The existing roadway consists of two 12-foot wide travel lanes with 170 feet of right of way (ROW). US-82 currently functions as a major arterial with posted speed limits ranging from a high of 60 miles per hour (mph) to a low of 35 mph. Average daily traffic along the project area is projected to be 9,400 vehicles per day (vpd) in 2015, and 12,900 vpd in 2035.

The project area does not presently have any paved sidewalks. The entire project area has been disturbed from previous or current construction activities for street, utility, and residential development.

#### Planned Facility

The project proposes to construct a new concrete pavement from FM 1840 in DeKalb to SH 98 near New Boston. The typical width of pavement will be 50 feet to allow for a passing lane section comprised of two 12-foot lanes in the passing lane direction, one 12-foot lane in the opposite direction, one 4-foot shoulder in the passing direction, and one 10-foot shoulder in the opposite direction. Two parcels will be acquired for ROW to provide for a 30 mph design speed connection for FM 1840 at the beginning of the project.

#### Funding and Planning

The project has been identified as a Pass-Through Funding project, and is included in and is consistent with TxDOT's 2011-2014 Statewide Transportation Improvement Program (STIP). The STIP total project cost is \$31,903,500.00. Based on the Pass-Through Funding Agreement, construction of the project would utilize local funds (Bowie County) and TxDOT would reimburse Bowie County with a mix of Federal and State funds. The anticipated letting date is February 2013. The estimated time of completion is February 2015. See **Appendix D** for the STIP page.

#### Need and Purpose

The purpose of the proposed project is to improve mobility and safety within the project area. The proposed project is needed to accommodate existing and future traffic volumes along US-82, the pavement for which was constructed in 1946.

#### Alternatives

Three alternatives were considered for this project: 1) the No Build alternative, 2) reconstructing and widening to the north of US-82, and 3) reconstructing and widening to the south of US-82.

#### No Build Alternative

Under the No Build Alternative, the proposed project would not be constructed. The No Build Alternative would result in the continued roadway safety and mobility concerns. Implementation of the No Build Alternative would not meet the proposed project need and purpose.

# Alternative 2 (North Widening)

Widening the existing roadway to the north side of US-82 would fulfill the purpose and need of the proposed project; however, a large amount of ROW would be required to be purchased, and several displacements would occur. Acquiring the necessary ROW for the proposed project would not be a cost-effective option.

# *Alternative 3 (Preferred Alternative)*

The proposed alternative satisfies the need and purpose of the proposed project. Location of the proposed project predominantly within the existing ROW minimizes additional ROW.

# Bicycle and Pedestrian Accommodations

A recent federal policy statement on Bicycle and Pedestrian Accommodations, Regulations, and Recommendations by USDOT signed on March 11, 2010, emphasizes an increased commitment to, and investment in, bicycle facilities and walking networks to help meet goals for cleaner, healthier air; less congested roadways, and more livable, safe, cost-effective communities. This USDOT policy encourages the incorporation of safe and convenient walking and bicycling facilities into transportation projects. As modes of travel, walking and bicycling are healthy, efficient, low cost, and available to nearly everyone. Due to the rural nature of the project area, no bicycle or pedestrian facilities are planned as a result of this proposed project.

## Right of Way and Utility Adjustment

Almost all construction associated with the proposed project would take place within the existing ROW. Two ROW parcels for realigning the intersection of FM 1840 and some easements for realigning intersecting roads and driveways are anticipated. Although acquisition of additional ROW is required, no relocations or displacements would occur. Existing ROW along US-82 is typically 170 feet in width. Approximately 0.33 acres of additional ROW, from two parcels, would be required for the proposed project. Additionally, approximately 0.73 acres of temporary easements would be required. The proposed ROW acquisition would be done in accordance with the Uniform Relocation Assistance and Real Property Acquisition Policy Act of 1970, as amended.

Utilities in the area include water and sanitary sewer, telecommunication, gas, and cable television. All utilities needing to be relocated will be relocated in advance of or during the US-82 reconstruction project. Preferably, these utilities would be relocated prior to construction of the proposed project.

# **Surrounding Area**

# Surrounding Terrain and Land Use

The project vicinity is comprised of generally flat topography with riparian features adjacent to Austin Chapel Branch and Red Bayou.

The proposed project traverses portions of DeKalb, Texas. The land in the vicinity of the proposed project is generally comprised of agricultural and rural residential land uses. Neither DeKalb nor Bowie County has comprehensive zoning regulations.

#### Soils

Information contained in the US Department of Agriculture (USDA) Web Soil Survey indicates the proposed project area is predominantly comprised of the following soil associations:

- Sawyer Silt Loam: Moderately well-drained, high available water capacity, greater than 80 inches to the restrictive feature, approximately 24 to 36 inches to the water table, classified as partially hydric.
- Eylau Sandy Loam: Moderately well-drained, moderately high available water capacity, 28 to 60 inches to the fragipan, approximately 24 to 36 inches to the water table, classified as partially hydric.
- Blevins Silt Loam: Well-drained, high available water capacity, greater than 80 inches to the restrictive feature, greater than 80 inches to the water table, classified as not hydric.

#### Public Facilities and Services

Woodman Cemetery is located adjacent to the proposed project corridor. The cemetery entrance is located on the north side of the project corridor, offset of FM 1840 to the south. The proposed project would not affect the access to the cemetery. Additionally, Malta School is located on the north side of the project area at the northeast corner of the intersection of US-82 and County Road 2789. The main entrances to the school are located off of County Road 2789. Therefore, the proposed project would not affect access to the school.

No other public facilities such as parks, hospitals, or fire/police stations are located within or immediately adjacent to the project corridor. Therefore, the construction, operation, and maintenance of the proposed project would not adversely affect public facilities.

#### Natural Setting

The project area is located in a rural setting comprised of agricultural fields and rural residential land. The project area crosses Austin Chapel Branch and Red Bayou.

Natural vegetation included loblolly pine, shortleaf pine, southern red oak, post oak, white oak, hickory, and sweetgum; also mid and tall grasses such as yellow Indiangrass, pinehill bluestem,

narrowleaf wood oats, and panicums. American beautyberry, sumac, greenbriar, and hawthorn are part of the understory.

#### **Specific Areas of Environmental Concern**

#### **Socioeconomics**

# Community Impacts

Approximately 0.33 acres of additional ROW is proposed for the project. No changes to travel patterns would occur. Existing access would be maintained during and after construction.

# Limited English Proficiency

Executive Order (E.O.) 13166, "Improving Access to Services for Persons with Limited English Proficiency (LEP)" requires federal agencies to examine the services they provide and identify any need for services to those with LEP, and develop and implement a system to provide those services so that LEP persons can have meaningful access to them.

In order to determine the presence of a LEP population in the project area, census data was obtained for the block group located in the project area. Census 2010 data indicated that within Census Tract 116, Block Groups 3, 4, and 6; and Census Tract 115.01, Block Groups 1 and 2, encompassing the proposed project, there were a total of 5,924 people. Of this population, approximately 1.4 percent spoke English "less than very well."

A windshield survey revealed that there are no business signs or advertisements in non-English languages located along the proposed project. No public involvement is planned at this time; however, if it is determined to be necessary at a future date, reasonable steps would be taken to ensure that such persons have meaningful access to the programs, services, and information that TxDOT provides. These reasonable steps include providing bilingual staff (such as Spanish- or French-speaking staff) on request to explain the proposed project, and any mail-outs or correspondence would be provided as bilingual communications. Therefore, the requirements of EO 13166 appear to be satisfied.

#### Environmental Justice

EO 12898 "Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations" requires each Federal agency to "make achieving environmental justice part of its mission by identifying and addressing, as appropriate, disproportionately high and adverse human health or environmental effects of its programs, policies and activities on minority populations and low-income populations." FHWA has identified three fundamental principles of environmental justice:

- 1. To avoid, minimize or mitigate disproportionately high and adverse human health or environmental effects, including social and economic effects, on minority populations and low income populations;
- 2. To ensure full and fair participation by all potentially affected communities in the transportation decision-making process;

3. To prevent the denial of, reduction in, or significant delay in the receipt of benefits by minority populations and low-income populations.

Disproportionately high and adverse human health or environmental effects are defined by FHWA as adverse effects that:

- 1. are predominately borne by a minority population and/or a low-income population; or
- 2. will be suffered by the minority population and/or low-income population and are appreciably more severe or greater in magnitude than the adverse effects that will be suffered by the non-minority population and/or non-low-income population.

According to the US Census Bureau 2010 Census, approximately 7.9 percent of the population in the blocks encompassing the proposed project area is considered to be minority. Not enough current data is available from the US Census Bureau to determine the percentage of the population in the block group encompassing the project area considered to be low-income (See Tables 1 and 2). A household income at or below the Department of Health and Human Services poverty guidelines (\$23,050 for a family of four in 2012) is considered low-income.

|                    |                     | Table 1        | 1: Minority                               | y Populatio  | on Perc        | entages  |                       |  |                          |
|--------------------|---------------------|----------------|---|--|----------------|--|-----------------------|--|--------------------------|
| Comparison<br>Area | Total<br>Population | White<br>Alone | Black or<br>African-<br>American<br>Alone | American<br>Indian<br>and<br>Alaska<br>Native<br>Alone | Asian<br>Alone | Native<br>Hawaiian<br>and<br>Other<br>Pacific<br>Islander<br>Alone | Some<br>Other<br>Race | Population<br>of Two or<br>More<br>Races | Hispanic<br>or<br>Latino |
| Census Tract 116   | 5,238               | 76.9%          | 17.5%                                     | 1.4%   | 0.2%           | 0.1%   | 2.1%                  | 1.9%                                     | 4.0%                     |
| Block Group 3      | 589                 | 48.2%          | 44.8%                                     | 1.0%   | 0.2%           | 0.0%   | 2.4%                  | 3.4%                                     | 2.7%                     |
| Block 3012         | 40                  | 72.5%          | 7.5%                                      | 2.5%   | 0.0%           | 0.0%   | 0.0%                  | 17.5%                                    | 0.0%                     |
| Block 3014         | 32                  | 78.1%          | 3.1%                                      | 3.1%   | 0.0%           | 0.0%   | 0.0%                  | 15.6%                                    | 15.6%                    |
| Block 3015         | 0                   | 0.0%           | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 0.0%                  | 0.0%                                     | 0.0%                     |
| Block 3016         | 4                   | 100.0%         | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 0.0%                  | 0.0%                                     | 0.0%                     |
| Block 3017         | 1                   | 0.0%           | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 100.0%                | 0.0%                                     | 0.0%                     |
| Block 3056         | 21                  | 81%            | 4.8%                                      | 4.8%   | 0.0%           | 0.0%   | 9.5%                  | 0.0%                                     | 9.5%                     |
| Block Group 4      | 1,257               | 75.3%          | 17.1%                                     | 1.3%   | 0.3%           | 0.1%   | 4.3%                  | 1.7%                                     | 6.5%                     |
| Block 4000         | 22                  | 90.9%          | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 0.0%                  | 9.1%                                     | 13.6%                    |
| Block Group 6      | 1,292               | 91.3%          | 4.2%                                      | 2.1%   | 0.2%           | 0.2%   | 0.7%                  | 1.4%                                     | 1.9%                     |
| Block 6000         | 75                  | 98.7%          | 0.0%                                      | 0.0%   | 1.3%           | 0.0%   | 0.0%                  | 0.0%                                     | 0.0%                     |
| Block 6004         | 157                 | 91.1%          | 0.0%                                      | 1.9%   | 0.0%           | 0.0%   | 4.5%                  | 2.5%                                     | 5.1%                     |
| Block 6006         | 27                  | 96.3%          | 0.0%                                      | 3.7%   | 0.0%           | 0.0%   | 0.0%                  | 0.0%                                     | 3.7%                     |
| Block 6007         | 63                  | 90.5%          | 0.0%                                      | 7.9%   | 0.0%           | 1.6%   | 0.0%                  | 0.0%                                     | 3.2%                     |
| Block 6008         | 0                   | 0.0%           | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 0.0%                  | 0.0%                                     | 0.0%                     |
| Block 6009         | 79                  | 97.5%          | 0.0%                                      | 0.0%   | 1.3%           | 0.0%   | 1.3%                  | 2.5%                                     | 0.0%                     |
| Block 6012         | 8                   | 100.0%         | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 0.0%                  | 0.0%                                     | 0.0%                     |
| Block 6013         | 2                   | 0.0%           | 100.0%                                    | 0.0%   | 0.0%           | 0.0%   | 0.0%                  | 0.0%                                     | 0.0%                     |
| Block 6017         | 0                   | 0.0%           | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 0.0%                  | 0.0%                                     | 0.0%                     |

|                     |                     | Table 1        | 1: Minority                               | y Populatio  | on Perc        | entages  |                       |  |                          |
|---------------------|---------------------|----------------|---|--|----------------|--|-----------------------|--|--------------------------|
| Comparison<br>Area  | Total<br>Population | White<br>Alone | Black or<br>African-<br>American<br>Alone | American<br>Indian<br>and<br>Alaska<br>Native<br>Alone | Asian<br>Alone | Native Hawaiian and Other Pacific Islander Alone | Some<br>Other<br>Race | Population<br>of Two or<br>More<br>Races | Hispanic<br>or<br>Latino |
| Block 6018          | 35                  | 100%           | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 0.0%                  | 0.0%                                     | 0.0%                     |
| Block 6019          | 0                   | 0.0%           | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 0.0%                  | 0.0%                                     | 0.0%                     |
| Block 6020          | 109                 | 95.4%          | 0.0%                                      | 0.9%   | 0.0%           | 0.9%   | 0.0%                  | 2.8%                                     | 0.0%                     |
| Block 6023          | 31                  | 96.8%          | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 3.2%                  | 0.0%                                     | 3.2%                     |
| Census Tract 115.01 | 7,910               | 67.9%          | 21.0%                                     | 0.7%   | 0.4%           | 0.0%   | 8.7%                  | 1.3%                                     | 12.9%                    |
| Block Group 1       | 1,835               | 91.5%          | 5.0%                                      | 1.0%   | 0.4%           | 0.0%   | 0.7%                  | 1.4%                                     | 2.8%                     |
| Block 1008          | 76                  | 93.4%          | 0.0%                                      | 2.6%   | 1.3%           | 0.0%   | 0.0%                  | 2.6%                                     | 0.0%                     |
| Block 1010          | 37                  | 78.4%          | 0.0%                                      | 8.1%   | 0.0%           | 0.0%   | 5.4%                  | 8.1%                                     | 13.5%                    |
| Block 1011          | 6                   | 100.0%         | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 0.0%                  | 0.0%                                     | 0.0%                     |
| Block 1012          | 0                   | 0.0%           | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 0.0%                  | 0.0%                                     | 0.0%                     |
| Block 1013          | 2                   | 100.0%         | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 0.0%                  | 0.0%                                     | 0.0%                     |
| Block 1014          | 0                   | 0.0%           | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 0.0%                  | 0.0%                                     | 0.0%                     |
| Block 1015          | 48                  | 100.0%         | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 0.0%                  | 0.0%                                     | 0.0%                     |
| Block Group 2       | 951                 | 93.7%          | 2.8%                                      | 1.6%   | 0.3%           | 0.0%   | 0.7%                  | 0.8%                                     | 2.9%                     |
| Block 2017          | 63                  | 100.0%         | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 0.0%                  | 0.0%                                     | 0.0%                     |
| Block 2022          | 52                  | 90.4%          | 7.7%                                      | 1.9%   | 0.0%           | 0.0%   | 0.0%                  | 0.0%                                     | 0.0%                     |
| Block 2023          | 12                  | 91.7%          | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 0.0%                  | 8.3%                                     | 8.3%                     |
| Block 2024          | 7                   | 100.0%         | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 0.0%                  | 0.0%                                     | 0.0%                     |
| Block 2025          | 43                  | 93.0%          | 0.0%                                      | 0.0%   | 2.3%           | 0.0%   | 2.3%                  | 2.3%                                     | 2.3%                     |
| Block 2027          | 25                  | 100.0%         | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 0.0%                  | 0.0%                                     | 0.0%                     |
| Block 2041          | 0                   | 0.0%           | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 0.0%                  | 0.0%                                     | 0.0%                     |
| Block 2042          | 0                   | 0.0%           | 0.0%                                      | 0.0%   | 0.0%           | 0.0%   | 0.0%                  | 0.0%                                     | 0.0%                     |
| Source: US Census   | Bureau, 201         | 10             |   |  |                |  |                       |  |                          |

| Table 2: Median Household Income and Poverty Level |                                |                                    |                                 |  |  |  |  |  |  |  |  |
|--|--------------------------------|------------------------------------|---------------------------------|--|--|--|--|--|--|--|--|
| Comparison Area                                    | Total<br>Population            | Individuals below<br>poverty level | Median household income in 2010 |  |  |  |  |  |  |  |  |
| Census Tract 116                                   | 5,238                          | 29.0%                              | \$36,996                        |  |  |  |  |  |  |  |  |
| Block Group 3                                      | 589                            | 34.2% (1999)                       | \$17,083 (1999)                 |  |  |  |  |  |  |  |  |
| Block Group 4                                      | 1,257                          | 31.9% (1999)                       | \$23,292 (1999)                 |  |  |  |  |  |  |  |  |
| Block Group 6                                      | 1,292                          | 29.2% (1999)                       | \$35,833 (1999)                 |  |  |  |  |  |  |  |  |
| Census Tract<br>115.01                             | 7,910                          | 14.8%                              | \$40,995                        |  |  |  |  |  |  |  |  |
| Block Group 1                                      | 1,835                          | N/A                                | N/A                             |  |  |  |  |  |  |  |  |
| Block Group 2                                      | 951                            | N/A                                | N/A                             |  |  |  |  |  |  |  |  |
| Source: US Census                                  | Source: US Census Bureau, 2010 |                                    |                                 |  |  |  |  |  |  |  |  |

While environmental justice populations are present within the project area, the proposed project consists of improvements that would serve the safety and transportation needs of all local residents. No relocations, displacements, or changes in access to residences would occur. Temporary lane encroachments or closures during project construction would cause traffic delays for all populations, but no long-term adverse impacts are expected to occur. Based on the above discussion and analysis, no disproportionately high and adverse impacts on minority or low-income populations are anticipated as a result of this proposed project. Therefore, the requirements of Executive Order 12898 are satisfied.

#### **Section 4(f) Properties**

The proposed project would not require the use of, nor substantially impair the purposes of any publicly owned land from a public park, recreational area, wildlife and waterfowl refuge lands or historic sites of national, state, or local significance; therefore, a 4(f) statement is not required.

#### **Cultural Resources**

Cultural resources are structures, buildings, archeological sites, districts (a collection of related structures, buildings, and/or archeological sites), cemeteries, and objects. Both federal and state laws require consideration of cultural resources during project planning. At the federal level, National Environmental Policy Act (NEPA) and the National Historic Preservation Act of 1966, among others, apply to transportation projects such as this one. In addition, state laws such as the Antiquities Code of Texas apply to this project. Compliance with these laws often requires consultation with the Texas Historic Commission (THC), Texas State Historic Preservation Officer (SHPO), and/or federally-recognized tribes to determine the project's effects on cultural resources. Review and coordination of this project followed approved procedures for compliance with federal and state laws.

#### **Historic Properties**

A review of the National Register of Historic Places (NRHP), the list of State Archeological Landmarks (SAL), and the list of Recorded Texas Historic Landmarks (RTHL) indicated that no historically significant resources have been previously documented within the area of potential effects (APE). It has been determined through consultation with the State Historic Preservation Officer (SHPO) that the APE for the proposed project is variable. The APE is the current ROW for the majority of the project. Where new ROW/construction easements are needed, the APE is those parcels which the ROW would be required from. A cultural resource survey conducted by TxDOT personnel in 2004 using a 300' APE revealed that there are no historic properties (built prior to 1954) located within the project APE. A further windshield/desktop survey in 2012 of the parcels that ROW is required from revealed no historic properties (built prior to 1967) within the APE.

Pursuant to Stipulation V, Undertakings with No Potential to Affect Historic Resources, of the First Amended Programmatic Agreement for Transportation Undertakings, (PA-TU) between the Federal Highway Administration (FHWA), the Texas State Historic Preservation Officer (SHPO), the Advisory Council on Historic Preservation, and the Texas Department of Transportation (TxDOT) and the Memorandum of Understanding (MOU), TxDOT Historians determined that the proposed action has no potential to affect historic properties and that individual project coordination with SHPO is not required.

#### **Archeological Resources**

Based on a previous archeological study (CSJ 0046-04-034) of the project area, no further investigation is warranted. A field investigation found no archeological sites within the project area. Consultation with federally-recognized Native American tribes with a demonstrated historic interest in the area was initiated on January 23, 2004. No objections or expressions of concern were received within the comment period. TxDOT and the THC/TSHPO consulted on the project impacts. The THC/TSHPO concurred that "no further work was recommended" on January 22, 2004. In the event that unanticipated archeological deposits are encountered during construction, work in the immediate area will cease, and TxDOT archeological staff will be contacted to initiate post-review discovery procedures.

#### Vegetation

According to the Texas Parks and Wildlife Department (TPWD) "Vegetation Types of Texas" publication (1984), the proposed project falls within the "Pine – Hardwood Forest" classification. The project area is also located in the Tertiary Uplands Ecological Region of Texas. This region has a great diversity of habitats and species. Prominent native trees include shortleaf pine, loblolly pine, southern red oak, post oak, black oak, white oak, hickories, and sweetgum. American beautyberry, sumac, greenbriar, and hawthorn are common understory species. Existing vegetation matches the description from the Vegetation Types of Texas. There was no unusual difference between vegetation located within the existing ROW and vegetation outside of the existing ROW.

Dominant herbaceous plants observed during a field reconnaissance include bahia grass (*Paspalum notatum*), bermuda grass (*Cynodon dactylon*), goldenrod (*Solidago Canadensis*), and other turf grasses. The existing ROW also includes black hickory (*Carya texana*), post oak

(*Quercus stellata*), and loblolly pine (*Pinus taeda*). The existing ROW is generally mowed and maintained. Herbaceous and woody vegetation would be permanently removed to accommodate the proposed improvements to US-82.

Approximately 20 acres of mature trees, typically black hickory and loblolly pine, would be impacted by the proposed project. These trees average a diameter at breast height (DBH) of 12 to 18 inches, and generally lie between the existing roadway and the former railroad track. Tree trimming maintenance of over hanging branches could be necessary during construction. Trimming or removal would be minimized as practical.

Unusual vegetation features observed within the existing and proposed ROW include:

- (a) unmaintained vegetation,
- (b) trees and shrubs along a fenceline adjacent to a field (fencerow vegetation), and
- (c) riparian vegetation.

The proposed project would not impact fencerow or unmaintained vegetation. However, the project would impact approximately 0.20 acres of riparian vegetation. According to observations from field visits, it appears that most of the areas within the existing ROW are comprised of maintained vegetation and mature trees.

According to a Memorandum of Agreement (MOA) between TxDOT and TPWD, special habitat features are classified as:

- (a) Bottomland hardwoods
- (b) Caves
- (c) Cliffs and bluffs
- (d) Native prairies (particularly those with climax species of native grasses and forbs)
- (e) Ponds
- (f) Seeps or springs
- (g) Snags or groups of snags
- (h) Water bodies
- (i) Existing bridges with known or easily observed bird or bat colonies.

Special habitat features identified within the project area include Red Bayou, Austin Chapel Branch, and Peters Branch, which are jurisdictional water bodies. There would be approximately 0.04 acre of permanent impacts to Red Bayou, 0.01 acre of permanent impacts to the Austin Chapel Branch, and 0.01 acre of permanent impacts to Peters Branch due to the proposed improvements and the maneuvering of construction equipment (see Table 4). BMPs would be used to avoid and/or minimize impacts to water quality. Measures would be taken to avoid the take of migratory birds, their occupied nests, eggs, or young.

In accordance with Provision (4) (A) (ii) of the Memorandum of Understanding (MOU) and MOA between TxDOT and TPWD, habitats given consideration for non-regulatory mitigation during project planning include the following:

- (a) Habitat for federal candidate species if mitigation would assist in the prevention of the listing of the species;
- (b) Rare vegetation series (S1, S2, or S3) that also locally provide habitat for a state-listed species;
- (c) All vegetation communities listed as S1 or S2, regardless of whether the series in question provide habitat for state-listed species;
- (d) Bottomland hardwoods, native prairies, and riparian sites; and
- (e) Any other habitat feature considered to be locally important.

The existing vegetation within the project area includes one of the above criteria for consideration of non-regulatory mitigation, riparian sites. Impacts to riparian vegetation would be minimized by limiting construction to the minimum required to properly construct the proposed project. The contractor would be encouraged to avoid and minimize impacts to vegetation where possible. Because of the minimal impacts to riparian vegetation, Bowie County does not propose compensatory mitigation for this activity. Additionally, there are also no caves, cliffs, bluffs, or evidence of bat colonies present in the project area.

Project specific triggers that initiate coordination with TPWD include the following:

- (1) might affect mature woody vegetation, dense mature brush, including any significant remnant native vegetation (e.g., undisturbed native prairie or bottomland hardwood, etc.)
- (2) are within the range and in suitable habitat of any state or federally-listed threatened or endangered species

Coordination with TPWD was initiated on March 26, 2012 and TPWD responded on April 3, 2012 with "No Comment" (see **Appendix E**).

## **Endangered Species Act**

The Endangered Species Act affords protection for federally listed threatened and endangered species and, where designated, critical habitat for these species. The U.S. Fish and Wildlife Service (USFWS) maintains a list of federally threatened and endangered species of potential

occurrence for each Texas county as does TPWD. TPWD maintains special species lists through the Natural Diversity Database (NDD) by county. The NDD identifies threatened or endangered species that have historically occurred in Bowie County. A review of the Texas Parks and Wildlife Department's (TPWD) Natural Diversity Database (NDD) was requested on February 23, 2012 and was evaluated in conjunction with geographical information systems (GIS).

One element of occurrence was documented within a 10-mile buffer of the proposed project. The Element Occurrence records indicate the bald eagle has been documented along the Red River where Texas, Oklahoma, and Arkansas meet, extending one mile on either side of the river, for approximately seven air miles. The proposed project is located approximately seven miles south of this corridor. However, no habitat suitable for the bald eagle was observed within or adjacent to the project area. No managed areas were documented within a 1.5-mile radius or 10-mile buffer of the proposed project. The NDD is used for potential presence data and cannot be interpreted as presence/absence data.

## Federal and State Threatened and Endangered Species

Table 3 addresses the Federal and State Threatened or Endangered Species for Bowie County, their listed status, habitat requirements, and anticipated effects from the proposed project.

This project would have no effect on any federal listed threatened or endangered species, its habitat, or designated critical habitat.

The project area contains habitat within or adjacent to the project area that may be potentially suitable for the Timber/Canebrake rattlesnake and Northern Scarlet Snake. Since these species may be encountered during construction, the contractor would be notified (via the EPIC sheet, general notes, and/or pre-construction meeting) of this potential and take the necessary measures to avoid harm to these species. The project is therefore not anticipated to cause adverse impacts to these state listed threatened species.

#### **State Species of Concern**

Table 3 addresses the State Species of Concern for Bowie County, their habitat requirements, and anticipated impacts from the proposed project. The project area contains habitat within or adjacent to the project area that may be suitable for the Plains Spotted Skunk, Rafinesque's Big-Eared Bat, Southeastern Myotis Bat, and Common Pimpleback. Since these species may be encountered during construction, the contractor would be notified (via the EPIC sheet, general notes, and/or pre-construction meeting) of this potential and take the necessary measures to avoid harm to these species. The project is therefore not anticipated to cause adverse impacts to state listed species of concern.

|                       | Table 3: Federal, State, Listed Threatened/Endangered Species, Texas Parks and Wildlife Department's Species of Concern, Bowie County, and Texas Natural Diversity Database Results |                 |   |                    |                   |                   |                             |  |  |  |
|-----------------------|---|-----------------|---|--------------------|-------------------|-------------------|-----------------------------|--|--|--|
| SPECIES               | FEDERAL<br>STATUS   | STATE<br>STATUS | DESCRIPTION OF HABITAT  | HABITAT<br>PRESENT | SPECIES<br>EFFECT | SPECIES<br>IMPACT | JUSTIFICA-<br>TION          |  |  |  |
| BIRDS                 |   |                 |   |                    |                   |                   |                             |  |  |  |
| American<br>Peregrine | DL*   | T               | Year-round resident and local breeder in west Texas, nests in | No                 | No effect         | No impact         | No impacts to habitat where |  |  |  |

| Bowle County, and Texas Natural Diversity Database Results |                   |                 |  |                    |                   |                   |  |  |  |  |
|--|-------------------|-----------------|--|--------------------|-------------------|-------------------|--|--|--|--|
| SPECIES  | FEDERAL<br>STATUS | STATE<br>STATUS | DESCRIPTION OF HABITAT   | HABITAT<br>PRESENT | SPECIES<br>EFFECT | SPECIES<br>IMPACT | JUSTIFICA-<br>TION   |  |  |  |
| Falcon<br>Falco<br>peregrinus<br>anatum                    |                   |                 | tall cliff eyries; also, migrant across state from more northern breeding areas in US and Canada, winters along coast and farther south; occupies wide range of habitats during migration, including urban, concentrations along coast and barrier islands; low-altitude migrant, stopovers at leading landscape edges such as lake shores, coastlines, and barrier islands. |                    |                   |                   | shorebirds, etc.<br>are likely to<br>gather.   |  |  |  |
| Arctic Peregrine Falcon Falco peregrinus tundrius          | DL*               |                 | Migrant throughout state from subspecies' far northern breeding range, winters along coast and farther south; occupies wide range of habitats during migration, including urban, concentrations along coast and barrier islands; low-altitude migrant, stopovers at leading landscape edges such as lake shores, coastlines, and barrier islands.                            | No                 | No effect         | No impact         | No impacts to<br>habitat where<br>shorebirds, etc.<br>are likely to<br>gather.   |  |  |  |
| Bachman's<br>Sparrow<br>Aimophila<br>aestivalis            | _                 | Т               | Open pine woods with scattered bushes and grassy understory in Pineywoods region, brushy or overgrown grassy hillsides, overgrown fields with thickets and brambles, grassy orchards; remnant grasslands in Post Oak Savannah region; nests on ground against grass tuft or under low shrub.   | No                 |                   | No impact         | Brushy habitat is present but is fragmented or routinely disturbed via mowing, maintenance or flooding during nesting season; habitat potential low. |  |  |  |
| Bald Eagle<br>Haliaeetus<br>leucocephalus                  | DL*               | Т               | Found primarily near rivers and large lakes; nests in tall trees or on cliffs near water; communally roosts, especially in winter; hunts live prey, scavenges, and pirates food from other birds.  | No                 | No effect         | No impact         | No large trees or cliffs in vicinity.  |  |  |  |
| Cerulean<br>Warbler<br>Dendroica<br>cerulea                | _                 |                 | Treetops of riverbank<br>woodlands, swamps, and<br>bottomlands; mainly<br>insectivorous.   | No                 |                   | No impact         | No riverbank<br>woodlands<br>present.  |  |  |  |

| SPECIES  | FEDERAL<br>STATUS | STATE<br>STATUS | DESCRIPTION OF HABITAT  | HABITAT<br>PRESENT | SPECIES<br>EFFECT | SPECIES<br>IMPACT | JUSTIFICA-<br>TION  |
|--|-------------------|-----------------|---|--------------------|-------------------|-------------------|---|
| Henslow's<br>Sparrow<br>Ammodramus<br>henslowii              | _                 |                 | Wintering individuals (not flocks) found in weedy fields or cut-over areas where lots of bunch grasses occur along with vines and brambles; a key component is bare ground for running/walking.   | No                 |                   | No impact         | No weedy fields<br>or areas with<br>bunch grasses<br>and bare ground<br>are present<br>within the<br>proposed project<br>area |
| Interior Least<br>Tern<br>Sterna<br>antillarum<br>athalassos | LE                | E               | Subspecies is listed only when inland (more than 50 miles from a coastline); nests along sand and gravel bars within braided streams, rivers; also know to nest on man-made structures (inland beaches, wastewater treatment plants, gravel mines, etc); eats small fish and crustaceans, when breeding forages within a few hundred feet of colony.  | No                 | No effect         | No impact         | Sandbars/gravel<br>bars not present.  |
| Peregrine<br>Falcon<br>Falco<br>peregrinus                   | DL*               | Т               | Both subspecies migrate across the state from more northern breeding areas in US and Canada to winter along coast and farther south; subspecies ( <i>F. p. anatum</i> ) is also a resident breeder in west Texas; the two subspecies' listing statuses differ, <i>F.p. tundrius</i> is no longer listed in Texas; but because the subspecies are not easily distinguishable at a distance, reference is generally made only to the species level; see subspecies for habitat. | No                 | No effect         | No impact         | No impacts to<br>habitat where<br>shorebirds, etc.<br>are likely to<br>gather.  |
| Piping Plover<br>Charadrius<br>melodus                       | Т*                | Т               | Wintering migrant along the<br>Texas Gulf Coast; beaches and<br>bayside mud or salt flats.  | No                 | No effect         | No impact         | No exposed<br>beaches,<br>mudflats, or<br>saltflats in the<br>vicinity.   |
| Sprague's Pipit<br>Anthus<br>spragueii                       | C*                |                 | Only in Texas during migration and winter, mid-September to early April; short to medium distance, diurnal migrant; strongly tied to native upland prairie, can be locally common in coastal grasslands, uncommon to rare further west; sensitive to patch size and avoids edges.   | No                 | No Effect         | No impact         | No native<br>upland prairie or<br>coastal<br>grasslands are<br>present within<br>the proposed<br>project area                 |

| SPECIES   | FEDERAL<br>STATUS | STATE<br>STATUS | DESCRIPTION OF HABITAT  | HABITAT<br>PRESENT | SPECIES<br>EFFECT | SPECIES<br>IMPACT | JUSTIFICA-<br>TION  |
|---|-------------------|-----------------|---|--------------------|-------------------|-------------------|---|
| Wood Stork<br>Mycteria<br>americana             |                   | Т               | Forages in prairie ponds, flooded pastures or fields, ditches, and other shallow standing water, including saltwater; usually roosts communally in tall snags, sometimes in association with other wading birds (i.e. active heronries); breeds in Mexico and birds move into Gulf States in search of mud flats and other wetlands, even those associated with forested areas; formerly nested in Texas, but no breeding records since 1960. | Yes                |                   | No impact         | Very little<br>shallow<br>standing water<br>in the project<br>area to be<br>impacted. |
| FISHES  |                   |                 |   |                    |                   |                   |   |
| Blackside darter<br>Percina<br>maculata         | _                 | Т               | Red, Sulfur and Cypress River<br>basins; clear, gravelly streams;<br>prefers pools with some current,<br>or even quiet pools, to swift<br>riffles   | No                 |                   | No impact         | Clear, gravelly<br>streams not<br>impacted by the<br>proposed<br>project.             |
| Creek<br>chubsucker<br>Erimyzon<br>oblongus     | _                 | Т               | Tributaries of the Red, Sabine, Neches, Trinity, and San Jacinto rivers; small rivers and creeks of various types; seldom in impoundments; prefers headwaters, but seldom occurs in springs; young typically in headwater rivulets or marshes; spawns in river mouths or pools, riffles, lake outlets, upstream creeks.   | No                 | i                 | No impact         | Silt loads at Red<br>Bayou decrease<br>habitat use<br>potential.                      |
| Goldeye<br>Hiodon<br>alosoides                  | _                 |                 | Red River basin below reservoir; spawns spring to July in shallow firm-bottomed backwaters or gravel shoals in tributaries, eggs semibuoyant drift downstream or to quiet water; adults in quiet turbid water of medium to large lowland rivers, small lakes, marshes and muddy shallows connected to them; young feed on microcrustaceans and other inverts; adults on surface water insects, also frogs, fishes, and small mammals.         | No                 |                   | No impact         | Medium to large<br>lowland<br>river/small lakes<br>not present.                       |
| Orangebelly<br>darter<br>Etheostoma<br>radiosum | _                 |                 | Red through Angelina River<br>basins; just headwaters ranging<br>from high gradient streams to<br>more sluggish lowland streams,<br>gravel and rubble riffles   | No                 |                   | No impact         | No headwaters present.  |

| Dowle County, and Texas Natural Diversity Database Results |                   |                 |   |                    |                   |                   |  |  |  |
|--|-------------------|-----------------|---|--------------------|-------------------|-------------------|--|--|--|
| SPECIES  | FEDERAL<br>STATUS | STATE<br>STATUS | DESCRIPTION OF HABITAT  | HABITAT<br>PRESENT | SPECIES<br>EFFECT | SPECIES<br>IMPACT | JUSTIFICA-<br>TION   |  |  |
|  |                   |                 | preferred; eggs buried in gravel<br>and riffle raceways, post-larvae<br>live in quiet water, move into<br>progressively faster water as<br>they mature, young feed mostly<br>on copepods and cladocerans,<br>adults on mayfly and fly larvae,<br>spawn late February through<br>mid-April in eastern Texas. |                    |                   |                   |  |  |  |
| Paddlefish<br>Polyodon<br>spathula                         | _                 | Т               | Prefers large, free-flowing rivers, but will frequent impoundments with access to spawning sites; spawns in fast, shallow water over gravel bars; larvae may drift from reservoir to reservoir  | No                 |                   | No impact         | Large, free-<br>flowing<br>rivers/impound<br>ments not<br>present. |  |  |
| Shovelnose<br>sturgeon<br>Scaphirhynchus<br>platorynchus   | _                 | Т               | Open, flowing channels with<br>bottoms of sand or gravel;<br>spawns over gravel or rocks in<br>an area with a fast current; Red<br>River below reservoir and rare<br>occurrence in Rio Grande.  | No                 |                   | No impact         | Flowing channels with appropriate substrate not present.           |  |  |
| Taillight shiner<br>Notropis<br>maculatus                  | _                 |                 | Sulfur River and Big Cypress Bayou; mostly headwaters, typically large sluggish, mud- bottomed small to large streams and lakes, usually with some aquatic vegetation; spawns March-October in backwaters and pools; feeds mainly on insect larva and cladocerans, also algae.                              | No                 |                   | No impact         | Habitat not present.   |  |  |
| Western sand<br>darter<br>Ammocrypta<br>clara              | _                 |                 | Red and Sabine River basins;<br>clear to slightly turbid water of<br>medium to large rivers that have<br>moderate to swift currents,<br>primarily over extensive areas of<br>sandy substrate.   | No                 |                   | No impact         | Medium to large<br>river not<br>present.                           |  |  |
| INSECTS  |                   |                 | •   |                    |                   |                   |  |  |  |
| American<br>burying beetle<br>Nicrophorus                  | LE                |                 | Varies widely from oak-hickory<br>and coniferous forest ridge tops<br>or hillsides to riparian corridors  | No                 | No effect         | No impact         | Saturated soils/loose sandy soils                                  |  |  |

| SPECIES  | FEDERAL<br>STATUS | STATE<br>STATUS | DESCRIPTION OF HABITAT   | HABITAT<br>PRESENT | SPECIES<br>EFFECT | SPECIES<br>IMPACT | JUSTIFICA-<br>TION  |
|--|-------------------|-----------------|--|--------------------|-------------------|-------------------|---|
| americanus   |                   |                 | and valley floor pastures;<br>extremely xeric, saturated, or<br>loose sandy soils unsuitable;<br>adults primarily above ground,<br>eggs in soil adjacent to buried<br>carcass, teneral adults<br>overwinter in soil. |                    |                   |                   | present.  |
| MAMMALS  | I                 | 1               |  |                    | T.                | I                 | I   |
| Plains spotted<br>skunk<br>Spilogale<br>putorius<br>interrupta | _                 |                 | Catholic; open fields, prairies, croplands, fence rows, farmyards, forest edges, and woodlands; prefers wooded, brushy areas and tallgrass prairie.  | Yes                |                   | No impact         | Potential impacts to habitat would be minor, and the potential for encountering species during construction is low. |
| Black bear<br>Ursus<br>americanus                              | T/SA;NL           | Т               | Bottomland hardwoods and large tracts of inaccessible forested areas; due to field characteristics similar to Louisiana Black Bear (LT, T), treat all east Texas black bears as federal and state listed Threatened. | No                 | No effect         | No impact         | Inaccessible<br>forested area not<br>impacted.  |
| Rafinesque's<br>big-eared bat<br>Corynorhinus<br>rafinesquii   |                   | Т               | Roosts in cavity trees of bottomland hardwoods, concrete culverts, and abandoned manmade structures.   | Yes                |                   | No impact         | Potential impacts to habitat would be minor, and the potential for encountering species during construction is low. |
| Red wolf Canis rufus   | E*                | Е               | Extirpated; formerly known throughout eastern half of Texas in brushy and forested areas, as well as coastal prairies.   | No                 | No effect         | No impact         | Extirpated from Texas.  |
| Southeastern<br>myotis bat<br>Myotis<br>austroriparius         | _                 |                 | Roosts in cavity trees of<br>bottomland hardwoods, concrete<br>culverts, and abandoned man-<br>made structures.  | Yes                |                   | No impact         | Potential impacts to habitat would be minor, and the potential for encountering species during construction is low. |
| MOLLUSKS   |                   |                 |  |                    |                   |                   |   |
| Fawnsfoot  |                   |                 | Small and large rivers especially  | No                 |                   | None              | Insufficient  |

| SPECIES   | FEDERAL | STATE  | DESCRIPTION OF HABITAT   | HABITAT | SPECIES | SPECIES   | JUSTIFICA-  |
|---|---------|--------|--|---------|---------|-----------|---|
| Truncilla<br>donaciformis                                 | STATUS  | STATUS | on sand, mud, rocky mud, and<br>sand and gravel, also silt and<br>cobble bottoms in still to swiftly<br>flowing waters; Red (historic),<br>Cypress (historic), Sabine<br>(historic), Neches, Trinity, and<br>San Jacinto River basins.   | PRESENT | EFFECT  | IMPACT    | water in channel<br>and no suitable<br>substrate.   |
| Common<br>pimpleback<br>Quadrula<br>pustulosa             | _       |        | Small streams to larger rivers,<br>and associated with nearly every<br>bottom type except deep shifting<br>sands; Red River downstream of<br>Lake Texoma and possibly Big<br>Cypress Bayou and lower<br>Sulphur river basins.  | Yes     |         | None      | Potential impacts to habitat would be minor, and the potential for encountering species during construction is low. |
| Wabash pigtoe<br>Fusconaia flava                          | Ï       |        | Creeks to large rivers on mud, sand, and gravel from all habitats except deep shifting sands; found in moderate to swift current velocities; east Texas River basins, Red through San Jacinto River basins; elsewhere occurs in reservoirs and lakes with no flow.   | No      |         | None      | Insufficient<br>water in channel<br>and no suitable<br>substrate.   |
| White<br>heelsplitter<br>Lasmigona<br>complanata          | Ί       |        | Typically large rivers and streams with sluggish, turbid waters, on mud or mud-gravel bottoms; also smaller streams and reservoirs usually deep in soft mud or occasionally among rocks; quiet areas of otherwise swift streams; Red River with unsuccessful introductions into the upper Trinity River System.                  | No      |         | None      | Insufficient<br>water in channel<br>and no suitable<br>substrate.   |
| REPTILES  |         |        |  |         |         |           |   |
| Alligator<br>snapping turtle<br>Macrochelys<br>temminckii | _       | Т      | Perennial water bodies; deep water of rivers, canals, lakes, and oxbows; also swamps, bayous, and ponds near deep running water; sometimes enters brackish coastal waters; usually in water with mud bottom and abundant aquatic vegetation; may migrate several miles along rivers; active March-October; breeds April-October. | No      |         | None      | No deep water is present within the project area.   |
| Northern scarlet<br>snake<br>Cemophora<br>coccinea copei  | _       | Т      | Mixed hardwood scrub on sandy<br>soils; feeds on reptile eggs;<br>semi-fossorial; active April-<br>September.  | Yes     |         | No impact | Potential<br>impacts to<br>habitat would be<br>minor, and the<br>potential for<br>encountering<br>species during    |

FEDERAL STATE HABITAT SPECIES SPECIES

| SPECIES  | STATUS  | STATE | DESCRIPTION OF HABITAT   | PRESENT | EFFECT | IMPACT   | TION  |
|--|---|-------|--|---------|--------|--|---|
|  |   |       |  |         |        |  | construction is low.  |
| Timber/Canebr<br>ake rattlesnake<br>Crotalus<br>horridus | _   | Т     | Swamps, floodplains, upland pine and deciduous woodlands, riparian zones, abandoned farmland; limestone bluffs, sandy soil or black clay; prefers dense ground cover, i.e. grapevines or palmetto. | Yes     |        | May<br>impact  | Upland pine,<br>deciduous<br>woodlands, and<br>riparian zones<br>present within<br>project area. No<br>specimens<br>observed during<br>field surveys. |
| PLANTS   |   |       |  |         |        |  |   |
| Arkansas<br>meadow-rue<br>Thalictrum<br>arkansanum       | _   | _     | Mostly deciduous forests on<br>alluvial terraces and upper<br>drainages of hardwood slope<br>forests at contacts with<br>calcareous prairies; flowering<br>March-April, withering by<br>midsummer  | Yes     |        | No impact  | Site reconnaissance conducted during flowering season; no species observed.   |
| TPWD NDD<br>Results                                      | Occurrence within 10 mile buffer, but outside of 1.5 mile buffer.  243Cedar Elm-sugarberry Series ( <i>Ulmus crassifolia-celtis laevigata</i> series), Federal/State status-none. Occurrence within 10 mile buffer, but outside of 1.5 mile |       |  |         |        | Element of<br>Occurrence<br>more than 1.5<br>miles from<br>the proposed<br>project area. |   |

E – State or Federal Listed Endangered

EXPN- Experimental population, Non-Essential

T - State or Federal Listed Threatened

PT-Proposed Threatened

C – Federal Candidate for Listing

DL - Federally Delisted

Sources: U.S. Fish & Wildlife Service (March 7, 2012), Texas Parks & Wildlife Department, Wildlife Division, Diversity and Habitat Assessment Programs, County Lists of Texas Special Species (March 7, 2012), and Field Visit (February 21, 2012).

# **Migratory Bird Treaty Act**

The Migratory Bird Treaty Act of 1918 states that it is unlawful to kill, capture, collect, possess, buy, sell, trade, or transport any migratory bird, nest, young, feather, or egg in part or in whole, without a federal permit issued in accordance within the Act's policies and regulations. Between October 1 and February 15, the contractor would remove all old migratory bird nests from any structures that would be affected by the proposed project, and complete any bridge work and/or vegetation clearing. In addition, the contractor would be prepared to prevent migratory birds from building nests between February 15 and October 1, per the Environmental Permits, Issues,

<sup>&</sup>quot;-" - No designation occurring within identified county

<sup>&</sup>quot;blank" – Rare, but with no regulatory listing status

<sup>&</sup>quot;--" - No determination of effect or impact required because species lacks federal and/or state listing status

<sup>&</sup>quot;\*" – TPWD T&E species list indicates species could be present in identified county; however, USFWS T&E species list does not indicate a listing status for the species in the county

and Commitments (EPIC) plans. In the event that migratory birds are encountered on-site during project construction, adverse impacts on protected birds, active nests, eggs, and/or young would be avoided.

## Executive Order 13112 on Invasive Species

Implemented in February 1999, EO 13112 was established "to prevent the introduction of invasive species and provide for their control and to minimize the economic, ecological, and human health impacts that invasive species cause." Protective measures against the introduction of invasive species will be utilized during the construction phase and re-vegetation phase of this project.

## Executive Memorandum on Beneficial Landscaping

The Executive Memorandum on Beneficial Landscaping directs that agencies shall, where cost-effective and to the extent practicable:

- (a) use regionally native plants for landscaping;
- (b) design, use, or promote construction practices that minimize adverse effects on the natural habitat:
- (c) seek to prevent pollution by, among other things, reducing fertilizer and pesticide use, using integrated pest management techniques, recycling green waste, and minimizing runoff. Landscaping practices that reduce the use of toxic chemicals provide one approach for agencies to reach reduction goals established in Executive Order No. 12856, "Federal Compliance with Right-To-Know Laws and Pollution Prevention Requirements";
- (d) implement water-efficient practices, such as the use of mulches, efficient irrigation systems, audits to determine exact landscaping water-use needs, and recycled or reclaimed water and the selecting and sizing of plants in a manner that conserves water and controls soil erosion. Landscaping practices, such as planting regionally native shade trees around buildings to reduce air conditioning demands, can also provide innovative measures to meet the energy consumption reduction goal established in Executive Order No. 12902, "Energy Efficiency and Water Conservation at Federal Facilities"; and
- (e) create outdoor demonstrations incorporating native plants, as well as pollution prevention and water conservation techniques, to promote awareness of the environmental and economic benefits of implementing this directive. Agencies are encouraged to develop other methods for sharing information on landscaping advances with interested nonfederal parties.

These practices, to the extent practicable, will be followed during the revegetation phase of the project.

#### **Water Resources**

# Section 404 of the Clean Water Act: Jurisdictional Water and Wetlands

The placement of temporary or permanent dredge or fill material into the jurisdictional Waters of the US will be authorized under Nationwide Permit (NWP) 14 with a Pre-Construction Notification (PCN). The US Army Corps of Engineers (USACE) Tulsa District was consulted in regards to potential jurisdictional waters located within the project area. The USACE issued a Preliminary Jurisdictional Determination on May 16, 2012, finding three intermittent streams in the project area to be jurisdictional: Austin Chapel Branch, Peters Branch, and Red Bayou. Additionally, a wetland abutting Red Bayou was found to be jurisdictional and will be permitted in conjunction with activities at Red Bayou.

Waters of the U.S. and anticipated impacts are listed in Table 4.

|  | Table 4: Waters of the US and Anticipated Impacts |  |   |   |                                      |   |                             |              |
|--|---|--|---|---|--------------------------------------|---|-----------------------------|--------------|
| Name of Water<br>Body or other<br>location<br>indicators | Existing<br>Structure                             | Proposed<br>Work or<br>Structure           | Perm<br>Water<br>(acres<br>and<br>linear<br>feet) | wetlands or other Special Aquatic Sites (Acres) | Tempo Waters (acres and linear feet) | rary Fill Wetlands or other Special Aquatic Sites (Acres) | NWP<br>(Indicate<br>Number) | PCN<br>(Y/N) |
| Red Bayou and<br>Abutting Wetland<br>(STA 997)           | 3Barrel<br>8ftx7ft Box<br>Culvert                 | Extend<br>approximately<br>34 ft south     | 0.04  | 0.09  | 0.00                                 | 0.00  | 14                          | Y            |
| Peters Branch<br>(STA 891)                               | None  | Expand<br>Concrete<br>Pavement             | 0.01  | 0.00  | 0.00                                 | 0.00  | 14                          | N            |
| Austin Chapel<br>Branch (STA 805)                        | None  | Expand<br>Concrete<br>Pavement             | 0.01  | 0.00  | 0.00                                 | 0.00  | 14                          | N            |
| STA 971  | 3FT x 2 FT<br>Box Culvert                         | Replace with<br>longer box or<br>lengthen  | 0.00  | 0.00  | 0.00                                 | 0.00  | N/A                         | N/A          |
| STA 797  | 6FT x 5FT<br>Box Culvert                          | Replace with<br>longer box or<br>lengthen  | 0.00  | 0.00  | 0.00                                 | 0.00  | N/A                         | N/A          |
| STA 840  | 24" Pipe<br>Culvert                               | Replace with<br>longer pipe or<br>lengthen | 0.00  | 0.00  | 0.00                                 | 0.00  | N/A                         | N/A          |

The purpose of the proposed activity is to expand the linear transportation facility at Red Bayou and its abutting wetland, Peters Branch, and Austin Chapel Branch. Appropriate measures would be taken to maintain normal downstream flows and minimize flooding. Temporary fills would be placed in a manner that would not be eroded by expected high flows, and would be removed in their entirety. The affected area would be returned to pre-construction elevations and revegetated as appropriate. Stream channel modifications, including bank stabilization, would be limited to the minimum necessary to construct or protect the structure and the immediate vicinity of the project.

The activity would comply with all general and regional conditions applicable to NWP 14. A PCN for NWP 14 at Red Bayou and its abutting wetland would be required because greater than 0.10 acre would be impacted; a PCN for NWP 14 is not required at Peters Branch and Austin Chapel Branch. There is no potential to affect listed species or designated critical habitat, and there are no historic properties listed or eligible for listing on the National Register of Historic Places. The activities at Red Bayou and its abutting wetland, Peters Branch, and Austin Chapel Branch have been identified as single and complete projects as defined in the Nationwide Permits by the USACE and will therefore be permitted separately.

The Preliminary Jurisdictional Determination letter from the USACE is included as **Appendix F**.

# Section 401 of the Clean Water Act

General Condition 21 of the NWP Program requires applicants using NWP # 14 to comply with Section 401 of the CWA. Compliance with Section 401 requires the use of best management practices (BMPs) to manage water quality on construction sites. The Stormwater Pollution Prevention Plan (SW3P) would include at least one BMP from the 401 Water Quality Certification Conditions for Nationwide Permits as published by the TCEQ on April 26 2007. These BMPs would address each of the following categories:

- Category I (erosion control) would be addressed by applying temporary and permanent re-seeding, blankets, or matting to stabilize disturbed areas.
- Category II (sediment control) would be addressed by compost logs and berms (low velocity); temporary rock filter dams; temporary rock bedding at the construction exits or silt fence; and
- Category III (post construction total suspended solids control) would be addressed by the
  hydraulic design to limit structure outlet velocities; grading design generally consisting of
  4:1 or flatter slopes with permanent vegetative cover; using permanent seeding/block sod
  to establish vegetative lined channels; or permanent compost manufactured topsoil and
  seeding.

Other approved methods may be substituted if necessary using one of the BMPs from the identical category.

## **EO 11990, Wetlands**

Alternatives were reviewed as required by Executive Order 11990 on wetlands, and no practicable alternatives to placing fill within the wetlands currently located within ROW were identified other than making minor modifications to side ditch slopes.

## Rivers and Harbors Act of 1899

The proposed project does not involve work in or over a navigable water of the US; therefore, Section 9 and 10 of the Rivers and Harbors Act does not apply.

## Section 303(d) of the Clean Water Act

Runoff from the proposed project would not discharge directly into a Section 303(d) listed threatened or impaired water, or into a stream within 5 miles upstream of a Section 303(d) listed threatened or impaired water. The 2010 303(d) list was utilized in this assessment.

# Section 402 of the Clean Water Act

The proposed project would disturb more than five acres; therefore, a SW3P would be prepared and implemented, and a construction site notice would be posted on the construction site. A Notice of Intent (NOI) would be required. The SW3P would utilize the temporary control measures as outlined in TxDOT's manual "Standard Specifications for the Construction of Highways, Streets, and Bridges."

The project is not located within the boundaries of a Municipal Separate Storm Sewer System (MS4).

#### **Floodplains**

Bowie County is a participant in the National Flood Insurance Program. A portion of the proposed project is located within the Federal Emergency Management Agency-designated 100-year floodplain (Flood Insurance Rate Map Nos. 48037C0300D, October 19, 2010). The hydraulic design for this project would be in accordance with current FHWA and TxDOT design policies. The facility would permit the conveyance of the 100-year flood, inundation of the roadway being acceptable, without causing substantial damage to the facility, stream, or other property. The proposed project would not increase the base flood elevation to a level that would violate applicable floodplain regulations and ordinances. Coordination with the local Floodplain Administrator would be required.

#### Trinity River Corridor Development Certificate

The project is not within the Trinity River Corridor Development Regulatory Zone; therefore, a Corridor Development Certificate (CDC) permit would not be required.

## Prime, Unique, and Special Farmlands

Additional ROW is required for the project; therefore, Form CS-CPA 106, Farmland Conversion Impact Rating for Corridor-Type Projects, was utilized. A score of less than 60 was found for both parts of the form; therefore, no coordination with the Natural Resources Conservation Service is required.

#### **Noise Assessment**

This analysis was accomplished in accordance with TxDOT's (FHWA approved) Guidelines for Analysis and Abatement of Roadway Traffic Noise (2011).

Sound from highway traffic is generated primarily from a vehicle's tires, engine, and exhaust. It is commonly measured in decibels and is expressed as "dB."

Sound occurs over a wide range of frequencies. However, not all frequencies are detectable by the human ear; therefore, an adjustment is made to the high and low frequencies to approximate the way an average person hears traffic sounds. This adjustment is called A-weighting and is expressed as "dB(A)."

Also, because traffic sound levels are never constant due to the changing number, type, and speed of vehicles, a single value is used to represent the average or equivalent sound level and is expressed as "Leq."

The traffic noise analysis typically includes the following elements:

- Identification of land use activity areas that might be impacted by traffic noise.
- Determination of existing noise levels.
- Prediction of future noise levels.
- Identification of possible noise impacts.
- Consideration and evaluation of measures to reduce noise impacts.

The FHWA has established the following Noise Abatement Criteria (NAC) for various land use activity areas that are used as one of two means to determine when a traffic noise impact would occur.

|                      | TABLE :           | 5: FHWA NO         | ISE ABATEMENT CRITERIA  |
|----------------------|-------------------|--------------------|---|
| Activity<br>Category | FHWA<br>dB(A) Leq | TxDOT<br>dB(A) Leq | Description of Land Use Activity Areas  |
| A                    | 57<br>(exterior)  | 56<br>(exterior)   | Lands on which serenity and quiet are of extra-<br>ordinary significance and serve an important public<br>need and where the preservation of those qualities is<br>essential if the area is to continue to serve its<br>intended purpose.   |
| В                    | 67<br>(exterior)  | 66<br>(exterior)   | Residential   |
| С                    | 67<br>(exterior)  | 66<br>(exterior)   | Active sport areas, amphitheaters, auditoriums, campgrounds, cemeteries, day care centers, hospitals, libraries, medical facilities, parks, picnic areas, places of worship, playgrounds, public meeting rooms, public or nonprofit institutional structures, radio studios, recording studios, recreation areas, Section 4(f) sites, schools, television studios, trails, and trail crossings. |
| D                    | 52<br>(interior)  | 51<br>(interior)   | Auditoriums, day care centers, hospitals, libraries, medical facilities, places of worship, public meeting rooms, public or nonprofit institutional structures, radio studios, recording studios, schools, and television studios   |
| Е                    | 72<br>(exterior)  | 71<br>(exterior)   | Hotels, motels, offices, restaurants/bars, and other developed lands, properties, or activities not included in A-D or F.   |

| TABLE 5: FHWA NOISE ABATEMENT CRITERIA |                   |                    |   |  |  |  |
|--|-------------------|--------------------|---|--|--|--|
| Activity<br>Category                   | FHWA<br>dB(A) Leq | TxDOT<br>dB(A) Leq | Description of Land Use Activity Areas  |  |  |  |
| F                                      |                   |                    | Agricultural, airports, bus yards, emergency services, industrial, logging, maintenance facilities, manufacturing, mining, rail yards, retail facilities, shipyards, utilities (water resources, water treatment, electrical), and warehousing. |  |  |  |
| G                                      |                   |                    | Undeveloped lands that are not permitted.   |  |  |  |

NOTE: primary consideration is given to <u>exterior</u> areas (Category A, B, C, or E) where frequent human activity occurs. However, <u>interior</u> areas (Category D) are used if exterior areas are physically shielded from the roadway, or if there is little or no human activity in exterior areas adjacent to the roadway.

A noise impact occurs when either the absolute or relative criterion is met:

Absolute criterion: the predicted noise level at a receiver approaches, equals, or exceeds the NAC. "Approach" is defined as one dB(A) below the FHWA NAC. For example: a noise impact would occur at a Category B residence if the noise level is predicted to be 66 dB(A) or above.

Relative criterion: the predicted noise level substantially exceeds the existing noise level at a receiver even though the predicted noise level does not approach, equal, or exceed the NAC. "Substantially exceeds" is defined as more than 10 dB(A). For example: a noise impact would occur at a Category B residence if the existing level is 54 dB(A) and the predicted level is 65 dB(A).

When a traffic noise impact occurs, noise abatement measures must be considered. A noise abatement measure is any positive action taken to reduce the impact of traffic noise on an activity area.

The FHWA traffic noise modeling software was used to calculate existing and predicted traffic noise levels. The model primarily considers the number, type, and speed of vehicles; highway alignment and grade; cuts, fills and natural berms; surrounding terrain features; and the locations of activity areas likely to be impacted by the associated traffic noise.

Existing and predicted traffic noise levels were modeled at receiver locations (Table 6 and **Appendix G**) that represent the land use activity areas adjacent to the proposed project that might be impacted by traffic noise and potentially benefit from feasible and reasonable noise abatement.

| TABLE 6:                | TRAFFIC N       | OISE         | LEVELS   | dB(A) Lo       | eq              | <b>1</b>     |
|-------------------------|-----------------|--------------|----------|----------------|-----------------|--------------|
| Representative Receiver | NAC<br>Category | NAC<br>Level | Existing | Predicted 2035 | Change<br>(+/-) | Noise Impact |
| R1 - Residential        | В               | 67           | 59       | 62             | +3              | N            |
| R2 - Residential        | В               | 67           | 60       | 62             | +2              | N            |
| R3 - Residential        | В               | 72           | 60       | 62             | +2              | N            |
| R4 - Residential        | В               | 67           | 62       | 64             | +2              | N            |
| R5 - Residential        | В               | 67           | 61       | 63             | +2              | N            |
| R6 - Residential        | В               | 67           | 60       | 62             | +2              | N            |
| R7 - Funeral Home       | Е               | 72           | 65       | 68             | +3              | N            |
| R8 - Residential        | В               | 67           | 60       | 64             | +4              | N            |
| R9 - Residential        | В               | 67           | 67       | 69             | +2              | Y            |
| R10 - Residential       | В               | 67           | 64       | 66             | +2              | Y            |
| R11 - Residential       | В               | 67           | 66       | 68             | +2              | Y            |
| R12 - Residential       | В               | 67           | 67       | 69             | +2              | Y            |
| R13 - Residential       | В               | 67           | 56       | 60             | +4              | N            |
| R14 - Residential       | В               | 67           | 66       | 68             | +2              | Y            |
| R15 - Residential       | В               | 67           | 65       | 67             | +2              | Y            |
| R16 - Residential       | В               | 67           | 59       | 64             | +5              | N            |
| R17 - Residential       | В               | 67           | 60       | 64             | +4              | N            |
| R18 - Residential       | В               | 67           | 60       | 63             | +3              | N            |
| R19 - Residential       | В               | 67           | 61       | 65             | +4              | N            |
| R20 - Residential       | В               | 67           | 61       | 65             | +4              | N            |
| R21 - Residential       | В               | 67           | 62       | 65             | +3              | N            |
| R22 - Residential       | В               | 67           | 61       | 65             | +4              | N            |
| R23 - Residential       | В               | 67           | 66       | 67             | +1              | Y            |
| R24 - Residential       | В               | 67           | 66       | 67             | +1              | Y            |
| R25 - Residential       | В               | 67           | 60       | 63             | +3              | N            |
| R26 - Residential       | В               | 67           | 65       | 67             | +2              | Y            |
| R27 - Residential       | В               | 67           | 64       | 66             | +2              | Y            |
| R28 - Residential       | В               | 67           | 65       | 67             | +2              | Y            |
| R29 - Residential       | В               | 67           | 65       | 67             | +2              | Y            |
| R30 - Residential       | В               | 67           | 65       | 67             | +2              | Y            |
| R31 - Residential       | В               | 67           | 66       | 68             | +2              | Y            |
| R32 - Church            | D               | 51           | 46       | 47             | +1              | N            |
| R33 - Residential       | В               | 67           | 66       | 67             | +1              | Y            |
| R34 - Residential       | В               | 67           | 65       | 66             | +1              | Y            |
| R35 - Residential       | В               | 67           | 65       | 66             | +1              | Y            |
| R36 - Residential       | В               | 67           | 66       | 67             | +1              | Y            |
| R37 - Residential       | В               | 67           | 66       | 67             | +1              | Y            |
| R38 - Residential       | В               | 67           | 65       | 66             | +1              | Y            |
| R39 - Church            | D               | 51           | 45       | 46             | +1              | N            |
| R40 - Residential       | В               | 67           | 65       | 66             | +1              | Y            |

|                         | TRAFFIC N       |              | 1        |                | _            |              |
|-------------------------|-----------------|--------------|----------|----------------|--------------|--------------|
| Representative Receiver | NAC<br>Category | NAC<br>Level | Existing | Predicted 2035 | Change (+/-) | Noise Impact |
| R41 - Residential       | В               | 67           | 68       | 68             | 0            | Y            |
| R42 - Restaurant        | Е               | 72           | 68       | 69             | +1           | N            |
| R43 - Residential       | В               | 67           | 69       | 67             | -2           | Y            |
| R44 - Residential       | В               | 67           | 67       | 66             | -1           | Y            |
| R45 - Residential       | В               | 67           | 64       | 66             | +2           | Y            |
| R46 - Residential       | В               | 67           | 66       | 67             | +1           | Y            |
| R47 - Coffee Shop       | Е               | 72           | 70       | 70             | 0            | N            |
| R48 - Residential       | В               | 67           | 67       | 68             | +1           | Y            |
| R49 - Residential       | В               | 67           | 58       | 61             | +3           | N            |
| R50 - Residential       | В               | 67           | 61       | 65             | +4           | N            |
| R51 - Residential       | В               | 67           | 61       | 63             | +2           | N            |
| R52 - Residential       | В               | 67           | 66       | 67             | +1           | Y            |
| R53 - Residential       | В               | 67           | 65       | 66             | +1           | Y            |
| R54 - Residential       | В               | 67           | 65       | 66             | +1           | Y            |
| R55 - Residential       | В               | 67           | 59       | 63             | +4           | N            |
| R56 - Residential       | В               | 67           | 61       | 64             | +3           | N            |
| R57 - Residential       | В               | 67           | 66       | 67             | +1           | Y            |
| R58 - Residential       | В               | 67           | 65       | 66             | +1           | Y            |
| R59 - Residential       | В               | 67           | 65       | 66             | +1           | Y            |
| R60 - Residential       | В               | 67           | 68       | 69             | +1           | Y            |
| R61 - Residential       | В               | 67           | 66       | 67             | +1           | Y            |
| R62 - Residential       | В               | 67           | 61       | 64             | +3           | N            |
| R63 - Residential       | В               | 67           | 65       | 66             | +1           | Y            |
| R64 - Residential       | В               | 67           | 64       | 66             | +2           | Y            |
| R65 - Residential       | В               | 67           | 65       | 66             | +1           | Y            |
| R66 - Residential       | В               | 67           | 65       | 66             | +1           | Y            |
| R67 - Residential       | В               | 67           | 67       | 68             | +1           | Y            |
| R68 - Residential       | В               | 67           | 66       | 67             | +1           | Y            |
| R69 - Residential       | В               | 67           | 60       | 64             | +4           | N            |
| R70 - Residential       | В               | 67           | 64       | 67             | +3           | Y            |
| R71 - Residential       | В               | 67           | 64       | 66             | +2           | Y            |
| R72 - Residential       | В               | 67           | 66       | 67             | +1           | Y            |
| R73 - Residential       | В               | 67           | 64       | 66             | +2           | Y            |
| R74 - Residential       | В               | 67           | 65       | 67             | +2           | Y            |
| R75 - Residential       | В               | 67           | 63       | 65             | +2           | N            |
| R76- Residential        | В               | 67           | 63       | 65             | +2           | N            |
| R77 - Residential       | В               | 67           | 65       | 66             | +1           | Y            |
| R78 - Residential       | В               | 67           | 62       | 65             | +3           | N            |
| R79 - Residential       | В               | 67           | 58       | 61             | +3           | N            |
| R80 - Residential       | В               | 67           | 65       | 66             | +1           | Y            |

| TABLE 6:                | TRAFFIC N       | OISE         | LEVELS   | dB(A) Lo       | eq           |              |
|-------------------------|-----------------|--------------|----------|----------------|--------------|--------------|
| Representative Receiver | NAC<br>Category | NAC<br>Level | Existing | Predicted 2035 | Change (+/-) | Noise Impact |
| R81 - Residential       | В               | 67           | 61       | 63             | +2           | N            |
| R82 - Residential       | В               | 67           | 55       | 57             | +2           | N            |
| R83 - Residential       | В               | 67           | 68       | 68             | 0            | Y            |
| R84 - Residential       | В               | 67           | 65       | 66             | +1           | Y            |
| R85 - Residential       | В               | 67           | 65       | 67             | +2           | Y            |
| R86 - Residential       | В               | 67           | 67       | 68             | +1           | Y            |
| R87 - Residential       | В               | 67           | 63       | 65             | +2           | N            |
| R88 - Residential       | В               | 67           | 67       | 68             | +1           | Y            |
| R89 - Residential       | В               | 67           | 65       | 66             | +1           | Y            |
| R90 - Residential       | В               | 67           | 67       | 67             | 0            | Y            |
| R91 - Residential       | В               | 67           | 67       | 68             | +1           | Y            |
| R92 - Residential       | В               | 67           | 64       | 66             | +2           | Y            |
| R93 - Residential       | В               | 67           | 65       | 66             | +1           | Y            |
| R94 - Residential       | В               | 67           | 65       | 67             | +2           | Y            |
| R95 - Residential       | В               | 67           | 65       | 67             | +2           | Y            |
| R96 - Residential       | В               | 67           | 60       | 65             | +5           | N            |
| R97 - Residential       | В               | 67           | 58       | 63             | +5           | N            |
| R98- Residential        | В               | 67           | 67       | 68             | +1           | Y            |
| R99 - School            | D               | 51           | 47       | 49             | +2           | N            |
| R100 - Residential      | В               | 67           | 66       | 66             | 0            | Y            |
| R101 - Residential      | В               | 67           | 66       | 66             | 0            | Y            |
| R102 - Residential      | В               | 67           | 65       | 67             | +2           | Y            |
| R103 - Residential      | В               | 67           | 67       | 68             | +1           | Y            |
| R104 - Restaurant       | Е               | 72           | 65       | 67             | +2           | N            |
| R105 - Residential      | В               | 67           | 58       | 62             | +4           | N            |
| R106 - Residential      | В               | 67           | 61       | 66             | +5           | Y            |
| R107 - Residential      | В               | 67           | 59       | 63             | +4           | N            |
| R108 - Residential      | В               | 67           | 61       | 65             | +4           | N            |
| R109 - Residential      | В               | 67           | 59       | 63             | +4           | N            |
| R110 - Residential      | В               | 67           | 67       | 68             | +1           | Y            |
| R111 - Residential      | В               | 67           | 66       | 67             | +1           | Y            |
| R112 - Residential      | В               | 67           | 65       | 67             | +2           | Y            |
| R113 - Residential      | В               | 67           | 60       | 63             | +3           | N            |
| R114- Residential       | В               | 67           | 61       | 65             | +4           | N            |
| R115 - Residential      | В               | 67           | 59       | 63             | +4           | N            |
| R116 - Residential      | В               | 67           | 60       | 64             | +4           | N            |
| R117 - Residential      | В               | 67           | 60       | 63             | +3           | N            |
| R118 - Residential      | В               | 67           | 67       | 68             | +1           | Y            |
| R119 - Residential      | В               | 67           | 59       | 62             | +3           | N            |
| R120 - Residential      | В               | 67           | 58       | 60             | +2           | N            |

| TABLE 6:                | TRAFFIC N       | OISE         | LEVELS   | dB(A) Lo       | eq           |              |
|-------------------------|-----------------|--------------|----------|----------------|--------------|--------------|
| Representative Receiver | NAC<br>Category | NAC<br>Level | Existing | Predicted 2035 | Change (+/-) | Noise Impact |
| R121 - Residential      | В               | 67           | 69       | 69             | 0            | Y            |
| R122 - Residential      | В               | 67           | 68       | 69             | +1           | Y            |
| R123 - Residential      | В               | 67           | 66       | 67             | +1           | Y            |
| R124 - Residential      | В               | 67           | 66       | 67             | +1           | Y            |
| R125 - Residential      | В               | 67           | 68       | 68             | 0            | Y            |
| R126 - Residential      | В               | 67           | 58       | 61             | +3           | N            |
| R127 - Residential      | В               | 67           | 58       | 61             | +3           | N            |
| R128 - Residential      | В               | 67           | 67       | 68             | +1           | Y            |
| R129 - Residential      | В               | 67           | 67       | 68             | +1           | Y            |
| R130 - Residential      | В               | 67           | 64       | 65             | +1           | N            |
| R131 - Residential      | В               | 67           | 60       | 64             | +4           | N            |
| R132 - Residential      | В               | 67           | 63       | 65             | +2           | N            |
| R133 - Residential      | В               | 67           | 65       | 67             | +2           | Y            |
| R134 - Residential      | В               | 67           | 67       | 68             | +1           | Y            |
| R135 - Residential      | В               | 67           | 66       | 67             | +1           | Y            |
| R136 - Residential      | В               | 67           | 65       | 66             | +1           | Y            |
| R137 - Residential      | В               | 67           | 65       | 66             | +1           | Y            |
| R138 - Residential      | В               | 67           | 62       | 65             | +3           | N            |
| R139 - Residential      | В               | 67           | 65       | 67             | +2           | Y            |
| R140 - Residential      | В               | 67           | 57       | 59             | +2           | N            |
| R141 - Residential      | В               | 67           | 59       | 61             | +2           | N            |
| R142 - Residential      | В               | 67           | 58       | 61             | +3           | N            |
| R143 - Residential      | В               | 67           | 67       | 68             | +1           | Y            |
| R144 - Residential      | В               | 67           | 58       | 60             | +2           | N            |
| R145 - Residential      | В               | 67           | 62       | 65             | +3           | N            |
| R146 - Residential      | В               | 67           | 60       | 63             | +3           | N            |
| R147 - Residential      | В               | 67           | 61       | 64             | +3           | N            |
| R148 - Residential      | В               | 67           | 62       | 65             | +3           | N            |
| R149 - Residential      | В               | 67           | 61       | 64             | +3           | N            |
| R150 - Residential      | В               | 67           | 61       | 64             | +3           | N            |
| R151 - Residential      | В               | 67           | 67       | 66             | -1           | Y            |
| R152 - Residential      | В               | 67           | 61       | 63             | +2           | N            |
| R153 - Residential      | В               | 67           | 64       | 66             | +2           | Y            |
| R154 - Church           | D               | 51           | 44       | 46             | +2           | N            |
| R155 - Driving School   | D               | 51           | 41       | 44             | +3           | N            |
| R156 - Residential      | В               | 67           | 65       | 68             | +3           | Y            |
| R157 - Residential      | В               | 67           | 64       | 67             | +3           | Y            |
| R158 - Residential      | В               | 67           | 58       | 61             | +3           | N            |
| R159 - Residential      | В               | 67           | 62       | 63             | +1           | N            |
| R160 - Residential      | В               | 67           | 67       | 68             | +1           | Y            |

| TABLE 6: TRAFFIC NOISE LEVELS dB(A) Leq |                 |              |          |                |              |              |
|---|-----------------|--------------|----------|----------------|--------------|--------------|
| Representative Receiver                 | NAC<br>Category | NAC<br>Level | Existing | Predicted 2035 | Change (+/-) | Noise Impact |
| R161 - Residential                      | В               | 67           | 65       | 66             | +1           | Y            |

As indicated in Table 6, the proposed project would result in a traffic noise impact and the following noise abatement measures were considered: traffic management, alteration of horizontal and/or vertical alignments, acquisition of undeveloped property to act as a buffer zone, and the construction of noise walls.

Before any abatement measure can be proposed for incorporation into the project, it must be both feasible and reasonable. In order to be "feasible," the abatement measure must be able to reduce the noise level at greater than 50% of impacted, first row receivers by at least five dB(A); and to be "reasonable," it must not exceed the cost-effectiveness criterion of \$25,000 for each receiver that would benefit by a reduction of at least five dB(A) and the abatement measure must be able to reduce the noise level at least one impacted, first row receiver by at least seven dB(A).

Traffic management: control devices could be used to reduce the speed of the traffic; however, the minor benefit of one dB(A) per five mph reduction in speed does not outweigh the associated increase in congestion and air pollution. Other measures such as time or use restrictions for certain vehicles are prohibited on state highways.

Alteration of horizontal and/or vertical alignments: any alteration of the existing alignment would displace existing businesses and residences, require additional ROW, and not be cost effective/reasonable.

Buffer zone: the acquisition of undeveloped property to act as a buffer zone is designed to avoid rather than abate traffic noise impacts and, therefore, is not feasible.

Noise walls: this is the most commonly used noise abatement measure. Noise walls were evaluated for each of the impacted receiver locations. Every property on the north side is accessed with a driveway that extends perpendicular from US-82 which makes the possibility of a wall unfeasible. On the south side of US-82, a noise wall was investigated to mitigate the predicted traffic noise level impact to two impacted residential properties. A wall 565' long and 10' high would provide up to 3 dB(A) reduction in noise level, which is less than the minimum desired buffer.

From the above analysis, noise walls would not be feasible or reasonable for any of the impacted receivers in Table 6 and, therefore, are not proposed for incorporation into the project. The ineffective conceptual wall barrier design would also exceed the \$25,000 per receiver cost-effectiveness criterion.

To avoid noise impacts that may result from future development of properties adjacent to the project, local officials responsible for land use control programs must ensure, to the maximum extent possible, no new activities are planned or constructed along or within the following predicted (2035) noise impact contours.

| LAND USE           | IMPACT<br>CONTOUR | DISTANCE from RIGHT of WAY |
|--------------------|-------------------|----------------------------|
| NAC category B & C | 66 dB(A)          | 155 to 220 feet            |
| NAC category E     | 71 dB(A)          | 67 to 122 feet             |

Noise associated with the construction of the project is difficult to predict. Heavy machinery, the major source of noise in construction, is constantly moving in unpredictable patterns. However, construction normally occurs during daylight hours when occasional loud noises are more tolerable. None of the receivers is expected to be exposed to construction noise for a long duration; therefore, any extended disruption of normal activities is not expected. Provisions will be included in the plans and specifications that require the contractor to make every reasonable effort to minimize construction noise through abatement measures such as work-hour controls and proper maintenance of muffler systems.

A copy of this traffic noise analysis will be available to local officials. On the date of approval of this document (Date of Public Knowledge), FHWA and TxDOT are no longer responsible for providing noise abatement for new development adjacent to the project.

#### **Hazardous Materials**

Based on the acquisition of additional ROW for the project, an Initial Site Assessment (ISA) was conducted to identify potential hazardous materials in the project area. The ISA consisted of the following actions: conducting a site survey, conducting a land use review, and conducting a regulatory database search. An analysis of the ISA data indicates hazardous materials impacts are not anticipated, and further investigation is not required.

Within the project limits, there is one registered petroleum storage tanks (RPST) facility located adjacent to the project. Skaggs Country Store at 3070 W US-82 is also listed as a leaking petroleum storage tank (LPST) site. The site survey and research into the historical land use did not reveal any other abandoned and/or active gasoline service stations.

A review of the Texas Commission on Environmental Quality (TCEQ) leaking petroleum storage tank (LPST) on-line database query indicated five LPST sites adjacent to the proposed project. According to the priority and status indicated in the list search, only minor soil contamination was indicated in three of the five adjacent LPST listings. TCEQ issued the final concurrence for four of these five listings and the cases are closed. In LPST case 117049 at the Skaggs Country Store, no apparent receptors were impacted and the case will be closed upon well plugging. LPST case 94335 occurred in 1989 and approximately 0.18 mile northwest of the westernmost extent of the proposed project area. Although TCEQ has not closed the case, quarterly well monitoring is ongoing, and TCEQ records indicate soil contamination is not a concern as a result of the incident. In this area of the proposed project, no significant lowering of the vertical alignment is required. Therefore, it is not anticipated that petroleum contamination would be encountered during construction.

This project will not involve the acquisition of known unresolved contamination where TxDOT could reasonably expect to assume liability for corrective action upon acquisition. In addition, this project does not involve known hazardous materials impacts that could be anticipated to adversely affect construction (e.g. cannot resolve before letting or during construction).

# **Magnuson-Stevens Fishery Conservation and Management Act**

There are no tidally-influenced waters in Bowie County; therefore, Essential Fish Habitat is not required to be addressed.

### Fish and Wildlife Coordination Act (FWCA)

The Fish and Wildlife Coordination Act (FWCA) of 1958 requires that federal agencies obtain comments from USFWS and TPWD. Since the proposed project is authorized under NWP 14, USFWS considers coordination to have been completed as part of their FHWA/TxDOT review last authorized and reissued in 2002.

#### Wild and Scenic Rivers

The proposed project area contains no Wild and Scenic Rivers. No Wild and Scenic Rivers would be impacted by the proposed project.

## **Air Analysis**

The proposed action is consistent with the FY 2011-2014 STIP. The project is located Bowie County, which is in an area in attainment of all National Ambient Air Quality Standards (NAAQS); therefore, the transportation conformity rules do not apply.

#### Carbon Monoxide (CO) Traffic Air Quality Analysis (TAQA)

Generally, passing lane projects are considered exempt from a transportation air quality analyses (TAQA) because they are intended to enhance traffic safety and improve traffic flow. The proposed action would not add capacity to an existing facility. Current and future emissions should continue to follow existing trends not being affected by this project. Due to the nature of this project, further carbon monoxide analysis was not required.

# Mobile Source Air Toxics (MSATs)

The purpose of this project is to reconstruct a rural roadway to add passing lanes. This project has been determined to generate minimal air quality impacts for CAAA criteria pollutants and has not been linked with any special Mobile Source Air Toxics (MSAT) concerns. As such, this project will not result in changes in traffic volumes, vehicle mix, basic project location, or any other factor that would cause an increase in MSAT impacts of the project from that of the nobuild alternative.

Moreover, Environmental Protection Agency (EPA) regulations for vehicle engines and fuels will cause overall MSAT emissions to decline significantly over the next several decades. Based on regulations now in effect, an analysis of national trends with EPA's MOBILE 6.2 model forecasts a combined reduction of 72 percent in the total annual emission rate for the priority MSAT from 1999 to 2050 while vehicle miles of travel are projected to increase by 145 percent. This will both reduce the background level of MSAT as well as the possibility of even minor MSAT emissions from this project.

#### Air Quality Construction Emissions

During the construction phase of this project, there can be temporary increases in air pollutant emissions from construction activities, equipment, and related vehicles. The primary construction related emissions are particulate matter (fugitive dust) from site preparation and construction, and non-road MSATs from construction equipment and vehicles. The primary MSAT emission related to construction is diesel particulate matter from diesel powered construction equipment and vehicles.

These emissions are temporary in nature (only occurring during actual construction) and it is not reasonably possible to estimate impacts from these emissions due to limitations of the existing models. However, the potential impacts of particulate matter emissions will be minimized by using fugitive dust control measures such as covering or treating disturbed areas with dust suppression techniques, sprinkling, covering loaded trucks, and other dust abatement controls as appropriate. The MSAT emissions will be minimized by measures to encourage use of EPA required cleaner diesel fuels, limits on idling, increasing use of cleaner burning diesel engines, and other emission limitation techniques, as appropriate.

However, considering the temporary and transient nature of construction related emissions as well as the mitigation actions to be utilized, it is not anticipated that emissions from construction of this proposed project will have any substantial impact on air quality in the area.

#### **Items of Special Nature**

There are no items of special nature or interest such as navigation or air-highway clearances, special permits, or agreements involved with the proposed project. The proposed project would not affect land or water uses within an area covered by a State Coastal Zone Management Program, nor would it impact coastal barrier resources. Coordination with the US Coast Guard would not be required.

#### **Environmental Permits, Issues, and Commitments**

This section summarizes the elements that constitute the Environmental Permits, Impacts, and Commitment (EPIC) Sheet. The EPIC sheet, found in the Environmental Tracking System, documents and communicates permit issues and environmental commitments that must be incorporated into the Plans, Specifications, and Estimates. The permits, impacts, and commitments relevant to the proposed project are as follows:

# I. Clean Water Act, Section 402 Texas Pollutant Discharge Elimination System (TPDES) Commitments

Since the proposed project would disturb more than five acres, TxDOT would be required to comply with the TCEQ Texas Pollutant Discharge Elimination System (TPDES) General Permit for Large Construction Activity. A Storm Water Pollution Prevention Plan (SW3P) would be prepared and implemented. A construction site notice would be posted on the construction site. A notice of intent is required.

#### II. Clean Water Act, Section 401 and 404 Compliance Commitments

Although coordination with the USACE regarding jurisdiction of the wetlands within the project area is ongoing, the project is expected to be eligible for NWP 14.

BMPs may include, but will not be limited to:

- Category I Erosion control: Temporary and permanent re-seeding, blankets, or matting to stabilize disturbed areas.
- Category II Sedimentation control: Compost logs and berms (low velocity); temporary rock filter dams; temporary rock bedding at the construction exits or silt fence; and,
- Category III Post construction total suspended solids control: Hydraulic design to limit structure outlet velocities; grading design generally consisting of 4:1 or flatter slopes with permanent vegetative cover; using permanent seeding/block sod to establish vegetative lined channels; or permanent compost manufactured topsoil and seeding.

#### III. Cultural Resources Commitment

In the event that unanticipated archeological deposits are encountered during construction, work in the immediate area will cease and TxDOT archeological staff will be contacted to initiate post-review discovery procedures.

#### IV. Vegetation Resources Commitment

Mature trees would be removed to accommodate the proposed project and the areas needed for construction purposes. Tree trimming maintenance of over- hanging branches could be necessary during construction. Trimming or removal would be minimized as practical.

#### V. Federal Listed, and Proposed Threatened and Endangered Species, Critical Habitat, State Listed Species, Candidate Species and Migratory Bird Treaty Act Commitment

The project area contains habitat within or adjacent to the project area that may be potentially suitable for the Plains Spotted Skunk, Rafinesque's Big-Eared Bat, Southeastern Myotis Bat, Common Pimpleback, Northern Scarlet Snake, and Timber/Canebrake Rattlesnake. Since these species may be encountered during construction, the contractor would be notified (via the EPIC sheet, general notes, and/or pre-construction meeting) of this potential and to take the necessary measures to avoid harm to these species.

#### Special Notes:

Between October 1 and February 15, the contractor would remove all old migratory bird nests from any structures that would be affected by the proposed project, and complete any bridge work and/or vegetation clearing. In addition, the contractor would be prepared to prevent migratory birds from building nests between February 15 and October 1, per the Environmental Permits, Issues, and Commitments (EPIC) plans. In the event that migratory birds are encountered on-site during project construction, adverse impacts on protected birds, active nests, eggs, and/or young would be avoided.

#### VI. Hazardous Materials or Contamination Issues Commitment

No action required for the proposed project.

#### VII. Other Environmental Issues Commitment

Measures to control fugitive dust would be considered and incorporated into the final design and construction specifications.

#### **Public Involvement**


The proposed Pass-Through Funding project was approved by Bowie County voters on May 14, 2011, by approving \$35 million in project bonds. Notice letters were sent to the two impacted property owners on March 28, 2012. Individual contact was subsequently made with the affected property owners in April 2012, regarding the proposed project.

The need for a public meeting is not anticipated for this project. TxDOT or Bowie County will contact local officials, schools, post office, and emergency services and inform them of the project. In addition, a news release will be issued to local newspapers and other media.

#### Conclusion

The proposed action meets the criteria for a Programmatic Categorical Exclusion (PCE) as defined in the *Programmatic Agreement for the Review and Approval of NEPA Categorically Excluded Transportation Projects (PA)*, executed by the Texas Division of the Federal Highway Administration (FHWA) and the Texas Department of Transportation (TxDOT) on November 7, 2011.

# APPENDIX A: GENERAL LOCATION MAP AND PROJECT TOPOGRAPHIC MAPS




LOCHNER

General Location Map US-82, Bowie County 0046-04-057

**Source: Bing Maps Scale: NTS** 










## **APPENDIX B: TYPICAL SECTIONS**





EXISTING
TYPICAL SECTIONS



| LOC                | HNER    | 1828 ESE Loop 3<br>Tyler, Texas 7570<br>TBPE Firm Reg. | 223   Sulfis 202<br>01<br>No. 10468 |
|--------------------|---------|--|-------------------------------------|
| FED.RD.<br>DIV.NQ. | PROJECT | NO.  | SHEET<br>NO.                        |
| -                  |         | 1.0  |                                     |

| FED.RD.<br>DIV.NQ. |       | SHEET<br>NQ. |             |
|--------------------|-------|--------------|-------------|
| 6                  |       |              | 41          |
| STATE              | DIST. |              | COUNTY      |
| TEXAS              | ATL   |              | BOWIE       |
| CONT.              | SECT. | JOB          | HIGHWAY NO. |
| 0046               | 04    | 057          | US 82       |






PROPOSED WB PASSING LANE SECTION

STA. 784-30.00 TO STA. 885-80.00 (GO TO SECTION (5))

STA. 994+30.00 TO STA. 1052+35.00
TRANSITION FROM (4) TO (5) STA. 1052+35.00 TO STA. 1058+45.28 (SEE PLAN PROFILE SHEETS FOR TRANSITION DETAILS?



#### NOTES:

- 1. PLANE ASPHALTIC CONCRETE PAVEMENT ON SHORADER, SALVAGE AND STOCKPILE PLANED MATERIALS AND REUSE IN PROPOSED CEWENT TREATED BASE AS PART OF ITEM 354 AGRA.
- SCARIFY, SALVAGE AND REPLACE GRAVEL BASE ON SHOULDER AS PART OF LITEM 251 WORK.
- PLANE ACP LEVEL-UP TAPER AND EXISTING ACP LUNGER ITEM 354 MORNS TO A NEAT VERTICAL TRIM LINE, INCORPORATE PLANED MATERIAL INTO COURT TREATMENT OPERATIONS AS PART OF ITEM 275 MORK.
- 4. FURNISH IY D GR 2 FLEXIBLE BASE AND MIX WITH SALVAGED GRAVEL BASE AND SALVACED PLANED ASPHALTIC CONCRETE PAVEMENT AS PART OF TIEM 247 WORK.
- 5. PRETREAT SUBCRADE HAVING A PL 3 to WITH LIME WHOSH ITEM ISO AS DIRECTED BY THE ENGINEER.


Document incomplete: Not intended for permit, bidding or construction.

Engineer: John B. Goodwin P.E. Registration Ma.: 63174 Date: 8/29/2012



SHEET 3 OF T

PROPOSED
TYPICAL SECTIONS



LOCHNER THE TOTAL THE STATE OF THE STATE OF

| ì | \$1 \$2. |       | 54-5 E T |        |        |
|---|----------|-------|----------|--------|--------|
| i | 6        |       |          |        |        |
|   | STATE    | 0157. |          | COUNTY |        |
|   | TEXAS    | ATL.  |          | DCALE  |        |
|   | t=ut.    | ster. | 1773     | итана  | AT NG. |
|   | C045     | 04    | C57      | US     | 92     |

# APPENDIX C: PHOTO LOG

# Photographic Inventory of Site Visit

Bowie County US-82 0046-04-057



Photo 1: Shell gas station located adjacent to eastern end of project area (USTs located approximately 200 feet north of centerline of US 82).



Photo 3: Utility service station located on south end of project area.



Photo 2: View of eastern extent of project area; view to southeast.



Photo 4: Typical vegetation near low-quality wetland on eastern end of project area.




Photo 5: Mottled soil characterized using Munsell Soil Chart on eastern extent of project area.



Photo 7: View of project area from eastern extent of project area; view to northwest.



Photo 6: Contact information for Utility Service yard adjacent to south portion of project area.



Photo 8: View of potentially jurisdictional wetlands within eastern extent of project area.



Photo 9: North side of box culvert over Red Bayou.



Photo 11: South side of box culvert over Red Bayou.



Photo 10: Red Bayou channel on north side of project area.



Photo 12: Riparian area between existing US-82 alignment and railbank.



Photo 13: Rural residential land adjacent to Red Bayou on north side of project area.



Photo 15: View of north side of current US-82 right of way, adjacent to Malta School.



Photo 14: Wetland within project area on south side of current US-82 alignment.



Photo 16: View of current US-82 alignment; junction with County Road 4105.



Photo 17: View of project area from Malta School; view to northwest.



Photo 19: View of project area near western extent of corridor; view to southeast.



Photo 18: View of auto repair shop located adjacent to project area.



Photo 20: View of project area near western extent of corridor; view to northwest.



Photo 21: LUST site located adjacent to project area on western extent of corridor.



Photo 23: View of project area near western extent of corridor.



Photo 22: View of typical vegetation within and adjacent to US-82 and railbank.

## **APPENDIX D: STIP PAGE**

#### PAGE: 3 OF 63

# STATEWIDE TRANSPORTATION IMPROVEMENT PROGRAM TIP FY 2011-2014

# TXDOT ATLANTA DISTRICT FY 2013

| DISTRICT   | COUNTY   | CSJ   | HWY                        | PHASE           | CITY                                 |                                    | PROJECT SPO   | NSOR                                    |             | YOE COST                  |
|--|--|---|----------------------------|-----------------|--------------------------------------|------------------------------------|---|---|-------------|---------------------------|
|  |  |   | -057 US 82<br>AY TO PROVII | C<br>DE PASSING | OTHER<br>LANES                       |                                    | REVISION DA<br>MPO PROJ NI<br>FUNDING CA  | UM:                                     | \$          | 29,471,437                |
| DESCR:<br>REMARKS<br>P7:   |  |   |                            |                 | PROJE<br>HISTO                       |                                    | RUCT 2 LANE RURA<br>OWIE COUNTY PASS  | L ROADWAY TO PI<br>S THROUGH PROJE      | ROVID<br>CT | DE PASSING                |
| TOTAL PRO  | JECT COST INFO   | RMATION                                     |                            |                 | AUTHORIZE                            | D FUNDING I                        | BY CATEGORY   | /SHARE                                  |             |                           |
| PRELIM ENG:  | \$ 1,444,100   | COST OF                                     |                            |                 | FEDERAL                              | STATE                              | LOCAL   | LC                                      |             | TOTAL                     |
| ROW PURCHASE<br>CONST COST:<br>CONST ENG:  |  | APPROVED PHASES:                            | TOTAL:                     | TR: \$<br>\$    | C \$                                 |                                    | \$ C  |   |             | 29,471,437*<br>29,471,437 |
| CONTING:<br>IND COSTS:<br>BND FINANCING:   | \$ 2,652,429<br>\$ 1,800,705   | \$ 29,471,437                               |                            |                 |                                      |                                    |   |   |             |                           |
| TOTAL PRJ COST   | <b>r:</b> \$ 36,694,886  | <br>  |                            |                 |                                      |                                    |   |   |             |                           |
| DISTRICT   | COUNTY   |   |                            |                 |                                      |                                    |   |   |             | v                         |
| <u> </u>   | COUNTY   | CSJ   | HWY                        | PHASE           | CITY                                 |                                    | PROJECT SPO   | NSOR                                    |             | YOE COST                  |
| 19 - ATLANTA LIMITS FROM 0.7 LIMITS TO: US   | UPSHUR<br>7 MI WEST OF US 29<br>3 259  | 0402-02 <sup>.</sup><br>59                  | -024 SH 154                | С               | CITY<br>OTHER                        |                                    | REVISION DA   | TE: 07/2010<br>UM:                      | \$          |                           |
| 19 - ATLANTA LIMITS FROM 0 LIMITS TO: US PROJECT WIDE                                | UPSHUR<br>7 MI WEST OF US 2  | 0402-02 <sup>.</sup><br>59                  | -024 SH 154                | С               | OTHER                                |                                    | REVISION DA   | TE: 07/2010<br>UM:                      | \$          |                           |
| 19 - ATLANTA LIMITS FROM 0.7 LIMITS TO: US   | UPSHUR<br>7 MI WEST OF US 29<br>3 259  | 0402-02 <sup>.</sup><br>59                  | -024 SH 154                | С               | OTHER                                | ECT WIDEN EX                       | REVISION DA   | TE: 07/2010<br>UM:                      | \$          |                           |
| 19 - ATLANTA LIMITS FROM 0.7 LIMITS TO: US PROJECT WIDE DESCR: REMARKS P7:           | UPSHUR<br>7 MI WEST OF US 29<br>3 259  | 0402-02-<br>59<br>WAY                       | -024 SH 154                | С               | OTHER PROJE                          | ECT WIDEN EX                       | REVISION DA<br>MPO PROJ NI<br>FUNDING CA  | TE: 07/2010<br>UM:<br>T(S): 1           | \$          |                           |
| 19 - ATLANTA LIMITS FROM 0.: LIMITS.TQ: US PROJECT WIDE DESCR: REMARKS P7: TOTAL PRO | UPSHUR 7 MI WEST OF US 2: 5 259 EN EXISTING ROAD   | 0402-02-<br>59<br>WAY<br>RMATION            | -024 SH 154                | С               | OTHER PROJE                          | ECT WIDEN EX                       | REVISION DA<br>MPO PROJ NI<br>FUNDING CA<br>ISTING ROADWAY                          | TE: 07/2010<br>UM:<br>T(S): 1           |             | 843,648                   |
| 19 - ATLANTA LIMITS FROM 0.1 LIMITS.TO: US PROJECT WIDE DESCR: REMARKS P7: TOTAL PRO | UPSHUR 7 MI WEST OF US 2: 5 259 EN EXISTING ROAD  JECT COST INFO \$ 41,336   | 0402-02-<br>59<br>WAY<br>RMATION<br>COST OF | -024 SH 154                | С               | OTHER  PROJE HISTO AUTHORIZE FEDERAL | ECT WIDEN EX<br>RY:<br>D FUNDING I | REVISION DA<br>MPO PROJ NI<br>FUNDING CA<br>ISTING ROADWAY<br>BY CATEGORYA<br>LOCAL | TE: 07/2010<br>UM:<br>T(S): 1<br>/SHARE |             |                           |
| 19 - ATLANTA LIMITS FROM 0.: LIMITS.TQ: US PROJECT WIDE DESCR: REMARKS P7: TOTAL PRO | UPSHUR 7 MI WEST OF US 2: 5 259 EN EXISTING ROAD  JECT COST INFO  \$ 41,336 : \$ 40,723 : \$ 843,648 \$ 63,274 \$ 59,055 \$ 51,547 | 0402-02-<br>59<br>WAY<br>RMATION<br>COST OF | -024 SH 154                | С               | OTHER PROJE HISTO                    | ECT WIDEN EX<br>RY:<br>D FUNDING I | REVISION DA MPO PROJ NI FUNDING CA ISTING ROADWAY  BY CATEGORY LOCAL                | TE: 07/2010<br>UM:<br>T(S): 1<br>/SHARE |             | 843,648<br>               |

## **APPENDIX E: COORDINATION DOCUMENTS**

January 22, 2004

Dr. James E. Bruseth Department of Antiquities Protection Texas Historical Commission P.O. Box 12276 Austin, Texas 78711

Dear Dr. Bruseth:

In accordance with Section 106 of the National Historic Preservation Act and the Antiquities Code of Texas, we are forwarding for your information review sheets and accompanying maps and other information for the attached projects reviewed since January 16, 2004.

The attached information includes projects that, in our opinion, do not warrant archeological surveys, projects that do not have the potential to affect historic properties, and/or projects where impact evaluations or surveys have been conducted and no archeological sites were found. We respectfully request your concurrence with our recommendations that these projects do not warrant further investigation and will not affect historic properties. Should any cultural remains be identified during construction, construction shall cease in that portion of the project and an archeologist from my staff will conduct an on-site evaluation of the find and consult further with your office.

Thank you for your attention to this matter. If you have any questions, please contact me at 416-2631.

Sincerely,

Owen Lindauer, Ph.D., Supervisor Archeological Studies Program

Environmental Affairs Division

Attachments

Cc:

FHWA, Project Managers, CRM Archeologists, SBW/file

Page: 1 of 1

#### ETS

#### ARCHEOLOGICAL COORDINATION

Inbox : 1/17/2004 To: 1/22/2004

#### Impact Evaluations, No Further Work Recommended

(Section 106 and ANTIQUITIES CODE OF TEXAS)

Date: 1/22/2004

| COUNTY   | DISTRICT | PROJECT | csu         | *F30/T20<br>Concur, no<br>further work | *F10/T10<br>Unable to<br>Concur |
|----------|----------|---------|-------------|--|---------------------------------|
| Angelina | Lufkin   | FM 1819 | 1795-02-013 | 1//                                    |                                 |
| Bowie    | Atlanta  | US 82   | 0046-04-034 | J.                                     |                                 |

Number of Projects:

2

JAN 23 2004 CRM

F. Lawerence Oaks

State Historic Preservation Officer and Executive Director

/-12-04 Date



# Federal Highway Administration

Texas Division Office 300 E. 8<sup>th</sup> Street, Rm. 826 Austin, Texas 78701

January 23, 2004

In Reply Refer To:

HB-TX

Mr. Kenneth Blanchard, Governor Jennifer Makaseah Absentee-Shawnee Executive Committee 2025 S. Gordon Cooper Drive Shawnee, OK 74801-9381

RE: CSJ: 0046-04-034 & 0046-04-046; US 82, from U.S. Highway 259 in De Kalb to IH 30 west of New Boston, Bowie County, Atlanta District

Dear Mr. Blanchard, Governor:

The above referenced transportation project is being considered for construction by the Federal Highway Administration (FHWA) and the Texas Department of Transportation (TxDOT), and we are in the process of conducting environmental studies for the project. The project is located in an area that may be of interest to your tribe. A brief summary of the proposed project, as well as a map of its general location and a map of the specific project location, are attached for your review. The summary includes information on archeological sites (if any) that are present within the area of the proposed project as well as the recommendations of TxDOT archeologists concerning the proposed project.

According to our procedures under Section 106 of the National Historic Preservation Act, we are writing to request your comments on historic properties of cultural or religious significance to your tribe that may be affected by the proposed undertaking. Any comments you may have on TxDOT's recommendations should also be provided. Please provide your comments within 30 days of receipt of this letter, and please reference the project information listed above. Further consultation with your tribe will continue for this project in the event that archeological sites are identified during our investigations or during construction.

Thank you for your attention to this matter. If you have questions, please contact me at 512/536-5968 or Waldo Troell, TxDOT Archeologist, at 512/416-2624.

Sincerely,

Paul D. Clutts, P. E.

Area Engineer

cc w/enclosures:

FHWA File Copy

Dianna F. Noble, P.E., Division Director/swb-file, TxDOT

Manual R. Flores, TxDOT-ENV, Project Manager

John Callison, TxDOT Atlanta District ENV Coordinator Waldo Troell, TxDOT Archeologist

#### **Project Description**

CSJ: 0046-04-034 & 0046-04-046; U.S.82, from U.S. Highway 259 in DeKalb to Interstate Highway 30 west of New Boston, Bowie County, Atlanta District.

The existing facility is a two-lane, undivided, rural roadway (two 12-ft-wide travel lanes and 8 to 10-ft-wide paved shoulders) with adjacent open drainage ditches within a 120-ft-wide right of way, except in urban areas where it varies between 70 and 100-ft-wide.

This project would improve safety and mobility along the 11.25-mile length of highway, by constructing two additional lanes to create a four-lane divided facility. The proposed facility would require an additional 94 acres of right of way, 84 of these acres would be obtained from an abandon railroad that is adjacent to the south side. Where the railroad diverges from U.S. 82 in DeKalb, all right of way between the highway and the railroad corridor would be purchased. Near New Boston, where the highway and railroad diverge, new right of way would be obtained from the south side of the existing highway.

A check of the Texas Archeological Sites Atlas (on December 8, 2003) revealed no recorded archeological sites within or adjacent to the proposed project area of potential effect.

An archeological impact evaluation was conducted on December 18, 2003 and revealed that both the existing and proposed right of way exhibited extensive disturbances. The disturbances were caused by construction and maintenance of the highway, railroad, utilities, buildings, and driveways. No settings with reasonable potential to contain archeological historic properties (36 CFR 800.16. (1)) or State Archeological Landmarks (13 TAC 26.12) were observed. Since the disturbance is so extensive, no further archeological work is warranted or proposed.

# County Location Map


County: Bowie

Project CSJ: 0046-04-034 &

0046-04-046

Project Name: US 82, from US Highway 259 in De Kalb to IH 30 west of New Boston,

Bowie County, Atlanta District.



CSJ:0046-04-034, BOWIE CO,

#### Standards of Uniformity for Historic Resources: Certification for PCE Projects

| SECTION 3: ENV HIST DETERMINATIONS  ADDITIONAL ACTIONS REQUIRED BY THE DISTRICT.  SOU TO BE RESUBMITTED WITH REQUESTED INFORMATION  [DO NOT WRITE on this page; for ENV HIST STAFF ONLY]  | Yes |
|---|-----|
| Project information is <u>insufficient</u> to determine level of Historic Resource Review and Consultation (see attached comments indicating why information is insufficient).  |     |
| Project information is sufficient to recommend that a <b>Reconnaissance Survey</b> be performed.** ENV HIST staff will consult with the District to specify survey needs and to develop a scope of work and a timeline for receiving contract deliverables. |     |
| Project information is sufficient to recommend that an <b>Intensive Survey</b> be performed.** ENV HIST staff will consult with the District to specify survey needs and develop a scope of work and a timeline for receiving contract deliverables.        |     |
| ADDITIONAL COMMENTS: No Survey regid  |     |

2

3

<sup>\*\*</sup> All work must meet appropriate Standards of Uniformity. Please consult with ENV HIST if District requires assistance through an ENV Scientific Services Contract.



March 26, 2012

Texas Parks & Wildlife Dept.

MAR 2 7 2012

Wildlife Habitat Assessment Program

**Environmental Document Coordination** CSJ: 0046-04-057 District: Atlanta

Highway: US 82 From: FM 1840

To: SH 98 **Bowie County** 

Ms. Kathy Boydston Texas Parks and Wildlife Department Wildlife Division - Wildlife Habitat Assessment Program 4200 Smith School Road Austin, Texas 78744

Dear Ms. Boydston:

Consistent with the Memorandum of Understanding signed by our two agencies, attached is a copy of the environmental document covering the subject project for your review and comment. Any comments you may have on this document will assist the Texas Department of Transportation (Department) in ensuring that the Department's projects are sensitive to the natural resources of the state. Please include the above CSJ number in your correspondence.

Please submit any comments you may have within 45 days from the date of this letter. If you do not have any comments on the document, please sign and date the bottom of this letter and return a copy to the Environmental Affairs Division. If no response is received after the 45 days have expired, we will proceed with project development. If you have any questions regarding this project please contact John Callison of the Atlanta District at (903) 799-1302 or by email at John.Callison@txdot.gov.

Sincerely.

Andrew Blair

Ecological Resources Branch Environmental Affairs Division

Enclosure

AEETY • EXPAND ECONOMIC OPPORTUNITY • IMPROVE AIR QUALTE US 2012 PRESERVE THE VALUE OF TRANSPORTATION ASSETS

An Equal Opportunity Employer

ENVIRONMENTAL AFFAIRS

# APPENDIX F: USACE PRELMINARY JURISDICTIONAL DETERMINATION



#### DEPARTMENT OF THE ARMY

CORPS OF ENGINEERS, TULSA DISTRICT 1645 SOUTH 101ST EAST AVENUE TULSA, OKLAHOMA 74128-4609

May 16, 2012 RECEIVED

Regulatory Office

MAY 21 2012

Mr. Alex Bartlett HW LOCHNER, Inc. 903 E. 104<sup>th</sup> St., Suite 800 Kansas City, MO 64114

Dear Mr. Bartlett:

This is in reference to your submitted delineation and request for a jurisdictional determination dated March 30, 2012. The review area consists of an 8.7 mile long segment of U.S. Route 82, located in the northern portion of Bowie County, Texas. More specifically, the review area is between Farm to Market Road 1840 in De Kalb, Texas and State Highway 98 near New Boston, Texas. We have reviewed the submitted data relative to Section 404 of the Clean Water Act (CWA).

We concur with your delineation that the review area does appear to contain waters of the United States. The intermittent streams, within the review area, identified as waters of the United States are Austin Chapel Branch, Peters Branch and Red Bayou. Additionally, there appears to be one jurisdictional wetland, identified in your delineation report as W3. The placement of dredged or fill material into these jurisdictional waters would require Department of the Army authorization pursuant to Section 404 of the CWA prior to commencement.

We encourage you to locate your proposed project away from any aquatic resources. Should you choose to site your operation near any stream or wetland, preparations should be made to maintain at least a 100-foot undisturbed buffer zone between the adjacent waterway and the borrow site.

This jurisdictional determination is based solely upon available office resources and not upon direct observation of the subject property. We believe this determination to be a reasonable assessment of the presence of jurisdictional waters on the site subject to Section 404 of the CWA. However, this is only a preliminary jurisdictional determination (PJD), and as such, is not a definitive description of on-site wetlands or U.S. Army Corps of Engineers (Corps) jurisdiction over the area. For an understanding of Administrative Appeal options regarding this PJD, please read the enclosed information sheet. Upon receipt of this letter please review, sign and return to this office the enclosed PJD form.

This determination has been conducted to identify the limits of the Corps CWA jurisdiction for the particular area identified in this request. This determination may not be valid for the wetland conservation provisions of the Food Security Act of 1985, as amended. If you or your tenant are USDA program participants, or anticipate participation in USDA programs, you should request a certified wetland determination from the local office of the Natural Resources Conservation Service prior to starting work.

If you desire to complete a "Customer Service Survey" on your experience with the Corps Regulatory Program, you are invited to visit <a href="http://per2.nwp.usace.army.mil/survey.html">http://per2.nwp.usace.army.mil/survey.html</a> on the internet at your convenience and submit your comments.

Your request has been assigned Identification No. SWT-2012-292. Please refer to this number during future correspondence. If you have any questions, contact Mr. Jamie R. Hyslop at 918-669-7618.

Sincerely,

Andrew R. Commer Chief, Regulatory Office

Enclosures

# ATTES OF ANTI-STATE OF ANTI-ST

#### DEPARTMENT OF THE ARMY CORPS OF ENGINEERS, TULSA DISTRICT 1645 SOUTH 101ST EAST AVENUE TULSA, OKLAHOMA 74128-4609

#### PRELIMINARY JURISDICTIONAL DETERMINATION FORM

#### BACKGROUND INFORMATION

- A. REPORT COMPLETION DATE FOR PRELIMINARY JURISDICTIONAL DETERMINATION (JD): May 15, 2012
- B. NAME AND ADDRESS OF PERSON REQUESTING PRELIMINARY JD: Mr. Alex Bartlett, HW LOCHNER, Inc, 903 E. 104<sup>th</sup> St., Suite 800, Kansas City, MO 64114.
- C. DISTRICT OFFICE, FILE NAME, AND NUMBER: Tulsa District, U.S. Route 82 reconstruction project, SWT-2012-292.
- D. PROJECT LOCATION(S) AND BACKGROUND INFORMATION: (USE THE ATTACHED TABLE TO DOCUMENT MULTIPLE WATERBODIES AT DIFFERENT SITES) SEE ATTACHED TABLE FOR ALL WATERS

State: Texas County/parish/borough: Bowie City: DeKalb Center coordinates of site (lat/long in degree decimal format): Lat. ° N, Long. ° W.

Universal Transverse Mercator:

Name of nearest waterbody: Red Bayou

Identify (estimate) amount of waters in the review area: Red Bayou

Non-wetland waters: 200 linear feet: 10-20 width (ft) and/or acres.

Cowardin Class: Riverine Stream Flow: Intermittent

Wetlands: 0.21+ acres. Abutting Red Bayou

Cowardin Class: Forested

Name of any water bodies on the site that have been identified as Section 10 waters:

Tidal:

Non-Tidal:

| E. | REVIEW PERFORMED FOR SITE EVALUATION (Check all that apply): |
|----|--|
|    | ○ Office (Desk) Determination. Date: May 15, 2012            |
|    | Field Determination. Date(s):                                |

This preliminary JD finds that there "may be" waters of the United States on the subject project site, and identifies all aquatic features on the site that could be affected by the proposed activity, based on the following information:

SUPPORTING DATA. Data reviewed for preliminary JD (check all that apply - checked items should be included in case file and, where checked and requested, appropriately reference sources below): Maps, plans, plots or plat submitted by or on behalf of the applicant/consultant: Mr. Alex Bartlett. □ Data sheets prepared/submitted by or on behalf of the applicant/consultant. Office concurs with data sheets/delineation report. Office does not concur with data sheets/delineation report. Data sheets prepared by the Corps: Corps navigable waters' study: USGS NHD data. USGS 8 and 12 digit HUC maps. ☑ U.S. Geological Survey map(s). Cite scale & quad name: 1:24,000 / DeKalb, Malta and New Boston, Texas. USDA Natural Resources Conservation Service Soil Survey. National wetlands inventory map(s). Cite name: New Boston, Texas. State/Local wetland inventory map(s): FEMA/FIRM maps: ☐ 100-year Floodplain Elevation is: (National Geodectic Vertical Datum of the control of th 1929) Photographs: Aerial (Name & Date):1 Meter Color, TX Aerials, most current Google Earth Pro. or Other (Name & Date): Previous determination(s). File no. and date of response letter: Other information (please specify): IMPORTANT NOTE: The information recorded on this form has not necessarily been verified by the Corps and should not be relied upon for later jurisdictional determinations. 09-22-12

Mr. Alex Bartlett

Jamie R. Hyslop

Regulatory Project Manager

Regulatory Office, 918-669-7618

Tulsa District U.S. Army Corps of Engineers

(Only use with multiple sites).

| Site number              | Latitude | Longitude | Cowardin<br>Class | Estimated amount of aquatic resource in review area | Class of aquatic resource |
|--------------------------|----------|-----------|-------------------|---|---------------------------|
| Austin Chapel     Branch | 33.4974  | -94.5540  | Riverine          | 200 linear feet                                     | Intermittent              |
| 2. Peters Branch         | 33.4889  | -94.5251  | Riverine          | 200 linear feet                                     | Intermittent              |
| 3.                       |          |           |                   |   |                           |
| 4.                       |          |           |                   |   |                           |
| 5.                       |          |           |                   |   |                           |

# NOTIFICATION OF ADMINISTRATIVE APPEAL OPTIONS AND PROCESS AND REQUEST FOR APPEAL

|       | icant: Mr. Alex Bartlett, Lochner, Inc | Date: May 16, 2012 |   |
|-------|--|--------------------|---|
| Attac | thed is:                               | See Section below  |   |
|       | INITIAL PROFFERED PERMIT (Standar      |                    | A |
|       | PROFFERED PERMIT (Standard Permit      | В                  |   |
|       | PERMIT DENIAL                          | C                  |   |
|       | APPROVED JURISDICTIONAL DETER          | D                  |   |
| X     | PRELIMINARY JURISDICTIONAL DET         | Е                  |   |

SECTION I - The following identifies your rights and options regarding an administrative appeal of the above decision. Additional information may be found at <a href="http://www.usace.army.mil/CECW/Pages/reg">http://www.usace.army.mil/CECW/Pages/reg</a> materials.aspx or Corps regulations at 33 CFR Part 331.

A: INITIAL PROFFERED PERMIT: You may accept or object to the permit.

- ACCEPT: If you received a Standard Permit, you may sign the permit document and return it to the district engineer for final
  authorization. If you received a Letter of Permission (LOP), you may accept the LOP and your work is authorized. Your
  signature on the Standard Permit or acceptance of the LOP means that you accept the permit in its entirety, and waive all rights
  to appeal the permit, including its terms and conditions, and approved jurisdictional determinations associated with the permit.
- OBJECT: If you object to the permit (Standard or LOP) because of certain terms and conditions therein, you may request that the permit be modified accordingly. You must complete Section II of this form and return the form to the district engineer. Your objections must be received by the district engineer within 60 days of the date of this notice, or you will forfeit your right to appeal the permit in the future. Upon receipt of your letter, the district engineer will evaluate your objections and may: (a) modify the permit to address all of your concerns, (b) modify the permit to address some of your objections, or (c) not modify the permit having determined that the permit should be issued as previously written. After evaluating your objections, the district engineer will send you a proffered permit for your reconsideration, as indicated in Section B below.

# B: PROFFERED PERMIT: You may accept or appeal the permit

- ACCEPT: If you received a Standard Permit, you may sign the permit document and return it to the district engineer for final
  authorization. If you received a Letter of Permission (LOP), you may accept the LOP and your work is authorized. Your
  signature on the Standard Permit or acceptance of the LOP means that you accept the permit in its entirety, and waive all rights
  to appeal the permit, including its terms and conditions, and approved jurisdictional determinations associated with the permit.
- APPEAL: If you choose to decline the proffered permit (Standard or LOP) because of certain terms and conditions therein, you
  may appeal the declined permit under the Corps of Engineers Administrative Appeal Process by completing Section II of this
  form and sending the form to the division engineer. This form must be received by the division engineer within 60 days of the
  date of this notice.
- C: PERMIT DENIAL: You may appeal the denial of a permit under the Corps of Engineers Administrative Appeal Process by completing Section II of this form and sending the form to the division engineer. This form must be received by the division engineer within 60 days of the date of this notice.
- D: APPROVED JURISDICTIONAL DETERMINATION: You may accept or appeal the approved JD or provide new information.
- ACCEPT: You do not need to notify the Corps to accept an approved JD. Failure to notify the Corps within 60 days of the date
  of this notice, means that you accept the approved JD in its entirety, and waive all rights to appeal the approved JD.
- APPEAL: If you disagree with the approved JD, you may appeal the approved JD under the Corps of Engineers Administrative
  Appeal Process by completing Section II of this form and sending the form to the division engineer. This form must be received
  by the division engineer within 60 days of the date of this notice.
- E: PRELIMINARY JURISDICTIONAL DETERMINATION: You do not need to respond to the Corps regarding the preliminary JD. The Preliminary JD is not appealable. If you wish, you may request an approved JD (which may be appealed), by contacting the Corps district for further instruction. Also you may provide new information for further consideration by the Corps to reevaluate the JD.

| SECTION II - REQUEST FOR APPEAL or OBJECT  | IONS TO AN INITIAL PRO   | FFERED PERMIT   |
|--|--|---|
| REASONS FOR APPEAL OR OBJECTIONS: (Descri initial proffered permit in clear concise statements. You may atta or objections are addressed in the administrative record.)  | be your reasons for appealing the d  | ecision or your objections to an                                  |
| ADDITIONAL INFORMATION: The appeal is limited to a review record of the appeal conference or meeting, and any supplemental clarify the administrative record. Neither the appellant nor the Coyou may provide additional information to clarify the location of  | I information that the review office<br>orps may add new information or a<br>information that is already in the a  | er has determined is needed to<br>nalyses to the record. However, |
| POINT OF CONTACT FOR QUESTIONS OR INFO   | RMATION:   |   |
| If you have questions regarding this decision and/or the appeal process you may contact:  Mr. Jamie Hyslop 918-669-7618  | also contact: Mr. Elliott Carman Administrative Appeals Review Of U.S. Army Corps of Engineers 1100 Commerce Street, Suite 831 Dallas, Texas 75242-1731 469-487-7061 |   |
| RIGHT OF ENTRY: Your signature below grants the right of enconsultants, to conduct investigations of the project site during the notice of any site investigation, and will have the opportunity to provide the conduct of the project site during the notice of any site investigation, and will have the opportunity to provide the conduct of the project site of the proje | e course of the appeal process. You participate in all site investigations.  | ou will be provided a 15 day                                      |
| G:   | Date:  | Telephone number:   |
| Signature of appellant or agent.   |  |   |

# APPENDIX G: TRAFFIC NOISE RECEIVERS

From FM 1840 to SH 98
Bowie County, Texas
CSJ 0046-04-057

Prepared for:

Texas Department of Transportation Atlanta District

Prepared by: LOCHNER

May 29, 2012



# **TABLE OF CONTENTS**

| Introduction | on  | 1  |
|--------------|---|----|
| US-82 Proj   | ect   | 1  |
| Characteris  | stics of Noise                                | 1  |
| Guidelines   |   | 2  |
| Methodolo    | ogy and Traffic Noise Impact Assessment       | 3  |
| Potential N  | Noise Abatement Measures                      | 9  |
| Construction | on Noise                                      | 10 |
| Coordinati   | on with Local Officials                       | 12 |
| Conclusion   | 1   | 13 |
|              | LIST OF TABLES                                |    |
| Table 1      | Noise Abatement Criteria                      |    |
| Table 2      | Traffic Noise Levels dB(A) Leq                |    |
| Table 3      | 66 and 71 dB(A) Contours for Design Year 2035 | 11 |
|              | LIST OF FIGURES                               |    |
| Exhibit 1.0  | Project Location                              | 14 |
| Exhibit 2.0  | - 2.18 Traffic Noise Receiver Locations       | 15 |
| Exhibit 3.0  | Project Location                              | 34 |



#### INTRODUCTION

This document discusses and describes the potential for noise effects from the US-82 roadway improvement from FM 1840 to SH 98 in Bowie County, Texas.

Noise is often defined as unwanted sound. Highway vehicle noise is primarily composed of engine exhaust, drive train, tire-roadway interaction and vehicle aerodynamics. Sound is a very subjective concept, and degrees of sound disturbance depend on several things: the amount and nature of the intruding noise, the relationship between the background noise and intruding noise, the type of activity where the noise is heard, and the time of day.

This analysis was accomplished in accordance with TxDOT's (FHWA approved) 2011 Guidelines for Analysis and Abatement of Roadway Traffic Noise.

# **US-82 PROJECT**

Bowie County, acting under a Pass Through Finance Agreement with The Texas Department of Transportation (TxDOT), plans to widen and improve US-82 in the TxDOT Atlanta District from FM 1840 to SH 98 in Bowie County. US-82 currently serves as a rural farm-to-market road consisting of two 12-foot travel lanes. The project proposes to construct new concrete pavement from FM 1840 in DeKalb to SH 98 near New Boston. The typical width of pavement will be 50 feet to allow for a passing lane section comprised of two twelve-foot lanes in the passing lane direction, one twelve-foot lane in the opposite direction, one four-foot shoulder in the passing direction, and one ten-foot shoulder in the opposite direction. The proposed project is approximately 8.7 miles in length. In DeKalb, a center turn lane section will be provided with a 16-foot center turn lane and 5-foot shoulders on both sides (50-foot total width). At the intersection of FM 2789 in Malta and at the intersection of SH 98, a center turn lane section will be provided with a 16-foot center turn lane and 10-foot shoulders. Additional turn and thru lanes will be provided at SH 98 to transition to the four-lane section proposed by TxDOT east of SH 98. Two parcels will be acquired for right of way to provide for a 30 mph design speed connection for FM 1840 at the beginning of the project.

#### CHARACTERISTICS OF NOISE

Sound from highway traffic is generated primarily from a vehicle's tires, engine, and exhaust. It is commonly measured in decibels and is expressed as "dB."

Sound occurs over a wide range of frequencies. However, not all frequencies are detectable by the human ear; therefore, an adjustment is made to the high and low frequencies to approximate the way an average person hears traffic sounds. This adjustment is called A-weighting and is expressed as "dB(A)."

Also, because traffic sound levels are never constant due to the changing number, type, and speed of vehicles, a single value is used to represent the average or equivalent sound level and is expressed as "Leq."

The traffic noise analysis typically includes the following elements:

- Identification of land use activity areas that might be impacted by traffic noise.
- Determination of existing noise levels.
- Prediction of future noise levels.
- Identification of possible noise impacts.
- Consideration and evaluation of measures to reduce noise impacts.

## **GUIDELINES**

Title 23 of the Code of Federal Regulations Part 772 (23 CFR 772) defines traffic noise impacts as those "impacts which occur when predicted traffic noise levels approach or exceed the Noise Abatement Criteria, or when the predicted traffic noise levels substantially exceed the existing noise levels."

The FHWA has established the following Noise Abatement Criteria (NAC) for various land use activity areas that are used as one of two means to determine when a traffic noise impact would occur. Table 1 summarizes the FHWA noise abatement criteria.

|                      | TABLE 1: NOISE ABATEMENT CRITERIA |                       |   |  |  |  |  |  |
|----------------------|-----------------------------------|-----------------------|---|--|--|--|--|--|
| Activity<br>Category | FHWA<br>dB(A)<br>Leq              | TxDOT<br>dB(A)<br>Leq | Description of Land Use Activity Areas  |  |  |  |  |  |
| А                    | 57<br>(exterior)                  | 56<br>(exterior)      | Lands on which serenity and quiet are of extra-ordinary significance and serve an important public need and where the preservation of those qualities is essential if the area is to continue to serve its intended purpose.  |  |  |  |  |  |
| В                    | 67<br>(exterior)                  | 66<br>(exterior)      | Residential   |  |  |  |  |  |
| С                    | 67<br>(exterior)                  | 66<br>(exterior)      | Active sport areas, amphitheaters, auditoriums, campgrounds, cemeteries, day care centers, hospitals, libraries, medical facilities, parks, picnic areas, places of worship, playgrounds, public meeting rooms, public or nonprofit institutional structures, radio studios, recording studios, recreation areas, Section 4(f) sites, schools, television studios, trails, and trail crossings. |  |  |  |  |  |
| D                    | 52<br>(interior)                  | 51<br>(interior)      | Auditoriums, day care centers, hospitals, libraries, medical facilities, places of worship, public meeting rooms, public or nonprofit institutional structures, radio studios, recording studios, schools, and television studios.  |  |  |  |  |  |
| E                    | 72<br>(exterior)                  | 71<br>(exterior)      | Hotels, motels, offices, restaurants/bars, and other developed lands, properties, or activities not included in A-D or F.   |  |  |  |  |  |
| F                    |                                   |                       | Agricultural, airports, bus yards, emergency services, industrial, logging, maintenance facilities, manufacturing, mining, rail yards, retail facilities, shipyards, utilities (water resources, water treatment, electrical), and warehousing.   |  |  |  |  |  |
| G                    |                                   |                       | Undeveloped lands that are not permitted.   |  |  |  |  |  |

NOTE: primary consideration is given to <u>exterior</u> areas (Category A, B, C, or E) where frequent human activity occurs. However, <u>interior</u> areas (Category D) are used if exterior areas are physically shielded from the roadway, or if there is little or no human activity in exterior areas adjacent to the roadway.

The FHWA has established absolute and relative criteria to more objectively determine when traffic sounds reach levels that result in impacts for humans. A noise impact occurs when either the absolute or relative criterion is met:

**Absolute criterion**: the predicted noise level at a receiver approaches, equals or exceeds the NAC. "Approach" is defined as one dB(A) below the NAC. For example: a noise impact would occur at a Category B residence if the noise level is predicted to be 66 dB(A) or above.

**Relative criterion**: the predicted noise level substantially exceeds the existing noise level at a receiver even though the predicted noise level does not approach, equal or exceed the NAC. "Substantially exceeds" is defined as more than 10 dB(A). For example: a noise impact would occur at a Category B residence if the existing level is 54 dB(A) and the predicted level is 65 dB(A).

When a traffic noise impact occurs, noise abatement measures must be considered. A noise abatement measure is any positive action taken to reduce the impact of traffic noise on an activity area.

#### METHODOLOGY AND TRAFFIC NOISE IMPACT ASSESSMENT

The FHWA traffic noise modeling software (TNM 2.5) was used to calculate existing and predicted traffic noise levels. The model primarily considers the number, type and speed of vehicles; highway alignment and grade; cuts, fills and natural berms; surrounding terrain features; and the locations of activity areas likely to be impacted by the associated traffic noise.

Existing and predicted traffic noise levels were modeled at receiver locations (Table 2 and Exhibits 2.1-2.18) that represent the land use activity areas adjacent to the proposed project that might be impacted by traffic noise and potentially benefit from feasible and reasonable noise abatement.

The TxDOT Atlanta District provided the traffic data for the analysis. During the peak hour, the US-82 facility would carry approximately 910 vehicles by 2015. By 2035, US-82 is projected to carry 1,240 vehicles. The peak hour vehicle fleet mix is 83.4% autos/ light duty vehicles, 2.6% medium trucks, and 14.0% heavy trucks. The directional split is 51/49.

As indicated in Table 2, the proposed project would result in a traffic noise impact. As depicted on the maps in Exhibits 2.1 to 2.18, about 96 receptors along the route would be impacted. Of the impacted receptors, 90 are residential properties largely located on the north side of US-82. Only two properties are located on the south side. The next section outlines potential noise abatement measures to mitigate predicted noise impacts.



| TABLE 2:                | TABLE 2: TRAFFIC NOISE LEVELS dB(A) Leq |              |          |                   |                 |              |  |
|-------------------------|---|--------------|----------|-------------------|-----------------|--------------|--|
| Representative Receiver | NAC<br>Category                         | NAC<br>Level | Existing | Predicted<br>2035 | Change<br>(+/-) | Noise Impact |  |
| R1 - Residential        | В                                       | 67           | 59       | 62                | +3              | N            |  |
| R2 - Residential        | В                                       | 67           | 60       | 62                | +2              | N            |  |
| R3 - Residential        | В                                       | 72           | 60       | 62                | +2              | N            |  |
| R4 - Residential        | В                                       | 67           | 62       | 64                | +2              | N            |  |
| R5 - Residential        | В                                       | 67           | 61       | 63                | +2              | N            |  |
| R6 - Residential        | В                                       | 67           | 60       | 62                | +2              | N            |  |
| R7 - Funeral Home       | Е                                       | 72           | 65       | 68                | +3              | N            |  |
| R8 - Residential        | В                                       | 67           | 60       | 64                | +4              | N            |  |
| R9 - Residential        | В                                       | 67           | 67       | 69                | +2              | Y            |  |
| R10 - Residential       | В                                       | 67           | 64       | 66                | +2              | Y            |  |
| R11 - Residential       | В                                       | 67           | 66       | 68                | +2              | Y            |  |
| R12 - Residential       | В                                       | 67           | 67       | 69                | +2              | Y            |  |
| R13 - Residential       | В                                       | 67           | 56       | 60                | +4              | N            |  |
| R14 - Residential       | В                                       | 67           | 66       | 68                | +2              | Y            |  |
| R15 - Residential       | В                                       | 67           | 65       | 67                | +2              | Y            |  |
| R16 - Residential       | В                                       | 67           | 59       | 64                | +5              | N            |  |
| R17 - Residential       | В                                       | 67           | 60       | 64                | +4              | N            |  |
| R18 - Residential       | В                                       | 67           | 60       | 63                | +3              | N            |  |
| R19 - Residential       | В                                       | 67           | 61       | 65                | +4              | N            |  |
| R20 - Residential       | В                                       | 67           | 61       | 65                | +4              | N            |  |
| R21 - Residential       | В                                       | 67           | 62       | 65                | +3              | N            |  |
| R22 - Residential       | В                                       | 67           | 61       | 65                | +4              | N            |  |
| R23 - Residential       | В                                       | 67           | 66       | 67                | +1              | Y            |  |
| R24 - Residential       | В                                       | 67           | 66       | 67                | +1              | Y            |  |
| R25 - Residential       | В                                       | 67           | 60       | 63                | +3              | N            |  |
| R26 - Residential       | В                                       | 67           | 65       | 67                | +2              | Y            |  |
| R27 - Residential       | В                                       | 67           | 64       | 66                | +2              | Y            |  |
| R28 - Residential       | В                                       | 67           | 65       | 67                | +2              | Y            |  |
| R29 - Residential       | В                                       | 67           | 65       | 67                | +2              | Y            |  |
| R30 - Residential       | В                                       | 67           | 65       | 67                | +2              | Y            |  |
| R31 - Residential       | В                                       | 67           | 66       | 68                | +2              | Υ            |  |
| R32 - Church            | D                                       | 51           | 46       | 47                | +1              | N            |  |
| R33 - Residential       | В                                       | 67           | 66       | 67                | +1              | Υ            |  |
| R34 - Residential       | В                                       | 67           | 65       | 66                | +1              | Υ            |  |
| R35 - Residential       | В                                       | 67           | 65       | 66                | +1              | Υ            |  |
| R36 - Residential       | В                                       | 67           | 66       | 67                | +1              | Υ            |  |
| R37 - Residential       | В                                       | 67           | 66       | 67                | +1              | Υ            |  |
| R38 - Residential       | В                                       | 67           | 65       | 66                | +1              | Υ            |  |

| TABLE 2: TRAFFIC NOISE LEVELS dB(A) Leq (Cont'd) |                 |              |          |                   |                 |              |
|--|-----------------|--------------|----------|-------------------|-----------------|--------------|
| Representative Receiver                          | NAC<br>Category | NAC<br>Level | Existing | Predicted<br>2035 | Change<br>(+/-) | Noise Impact |
| R39 - Church                                     | D               | 51           | 45       | 46                | +1              | N            |
| R40 - Residential                                | В               | 67           | 65       | 66                | +1              | Υ            |
| R41 - Residential                                | В               | 67           | 68       | 68                | 0               | Υ            |
| R42 - Restaurant                                 | Е               | 72           | 68       | 69                | +1              | N            |
| R43 - Residential                                | В               | 67           | 69       | 67                | -2              | Υ            |
| R44 - Residential                                | В               | 67           | 67       | 66                | -1              | Υ            |
| R45 - Residential                                | В               | 67           | 64       | 66                | +2              | Y            |
| R46 - Residential                                | В               | 67           | 66       | 67                | +1              | Υ            |
| R47 - Coffee Shop                                | Е               | 72           | 70       | 70                | 0               | N            |
| R48 - Residential                                | В               | 67           | 67       | 68                | +1              | Υ            |
| R49 - Residential                                | В               | 67           | 58       | 61                | +3              | N            |
| R50 - Residential                                | В               | 67           | 61       | 65                | +4              | N            |
| R51 - Residential                                | В               | 67           | 61       | 63                | +2              | N            |
| R52 - Residential                                | В               | 67           | 66       | 67                | +1              | Υ            |
| R53 - Residential                                | В               | 67           | 65       | 66                | +1              | Υ            |
| R54 - Residential                                | В               | 67           | 65       | 66                | +1              | Υ            |
| R55 - Residential                                | В               | 67           | 59       | 63                | +4              | N            |
| R56 - Residential                                | В               | 67           | 61       | 64                | +3              | N            |
| R57 - Residential                                | В               | 67           | 66       | 67                | +1              | Υ            |
| R58 - Residential                                | В               | 67           | 65       | 66                | +1              | Υ            |
| R59 - Residential                                | В               | 67           | 65       | 66                | +1              | Υ            |
| R60 - Residential                                | В               | 67           | 68       | 69                | +1              | Υ            |
| R61 - Residential                                | В               | 67           | 66       | 67                | +1              | Υ            |
| R62 - Residential                                | В               | 67           | 61       | 64                | +3              | N            |
| R63 - Residential                                | В               | 67           | 65       | 66                | +1              | Υ            |
| R64 - Residential                                | В               | 67           | 64       | 66                | +2              | Υ            |
| R65 - Residential                                | В               | 67           | 65       | 66                | +1              | Υ            |
| R66 - Residential                                | В               | 67           | 65       | 66                | +1              | Υ            |
| R67 - Residential                                | В               | 67           | 67       | 68                | +1              | Υ            |
| R68 - Residential                                | В               | 67           | 66       | 67                | +1              | Υ            |
| R69 - Residential                                | В               | 67           | 60       | 64                | +4              | N            |
| R70 - Residential                                | В               | 67           | 64       | 67                | +3              | Υ            |
| R71 - Residential                                | В               | 67           | 64       | 66                | +2              | Υ            |
| R72 - Residential                                | В               | 67           | 66       | 67                | +1              | Υ            |
| R73 - Residential                                | В               | 67           | 64       | 66                | +2              | Y            |
| R74 - Residential                                | В               | 67           | 65       | 67                | +2              | Υ            |
| R75 - Residential                                | В               | 67           | 63       | 65                | +2              | N            |
| R76- Residential                                 | В               | 67           | 63       | 65                | +2              | N            |

| TABLE 2: TRAF           | TABLE 2: TRAFFIC NOISE LEVELS dB(A) Leq (Cont'd) |              |          |                   |                 |              |  |
|-------------------------|--|--------------|----------|-------------------|-----------------|--------------|--|
| Representative Receiver | NAC<br>Category                                  | NAC<br>Level | Existing | Predicted<br>2035 | Change<br>(+/-) | Noise Impact |  |
| R77 - Residential       | В  | 67           | 65       | 66                | +1              | Y            |  |
| R78 - Residential       | В  | 67           | 62       | 65                | +3              | N            |  |
| R79 - Residential       | В  | 67           | 58       | 61                | +3              | N            |  |
| R80 - Residential       | В  | 67           | 65       | 66                | +1              | Y            |  |
| R81 - Residential       | В  | 67           | 61       | 63                | +2              | N            |  |
| R82 - Residential       | В  | 67           | 55       | 57                | +2              | N            |  |
| R83 - Residential       | В  | 67           | 68       | 68                | 0               | Y            |  |
| R84 - Residential       | В  | 67           | 65       | 66                | +1              | Y            |  |
| R85 - Residential       | В  | 67           | 65       | 67                | +2              | Y            |  |
| R86 - Residential       | В  | 67           | 67       | 68                | +1              | Y            |  |
| R87 - Residential       | В  | 67           | 63       | 65                | +2              | N            |  |
| R88 - Residential       | В  | 67           | 67       | 68                | +1              | Y            |  |
| R89 - Residential       | В  | 67           | 65       | 66                | +1              | Y            |  |
| R90 - Residential       | В  | 67           | 67       | 67                | 0               | Y            |  |
| R91 - Residential       | В  | 67           | 67       | 68                | +1              | Y            |  |
| R92 - Residential       | В  | 67           | 64       | 66                | +2              | Y            |  |
| R93 - Residential       | В  | 67           | 65       | 66                | +1              | Y            |  |
| R94 - Residential       | В  | 67           | 65       | 67                | +2              | Y            |  |
| R95 - Residential       | В  | 67           | 65       | 67                | +2              | Y            |  |
| R96 - Residential       | В  | 67           | 60       | 65                | +5              | N            |  |
| R97 - Residential       | В  | 67           | 58       | 63                | +5              | N            |  |
| R98- Residential        | В  | 67           | 67       | 68                | +1              | Y            |  |
| R99 - School            | D  | 51           | 47       | 49                | +2              | N            |  |
| R100 - Residential      | В  | 67           | 66       | 66                | 0               | Υ            |  |
| R101 - Residential      | В  | 67           | 66       | 66                | 0               | Υ            |  |
| R102 - Residential      | В  | 67           | 65       | 67                | +2              | Y            |  |
| R103 - Residential      | В  | 67           | 67       | 68                | +1              | Y            |  |
| R104 - Restaurant       | Е  | 72           | 65       | 67                | +2              | N            |  |
| R105 - Residential      | В  | 67           | 58       | 62                | +4              | N            |  |
| R106 - Residential      | В  | 67           | 61       | 66                | +5              | Υ            |  |
| R107 - Residential      | В  | 67           | 59       | 63                | +4              | N            |  |
| R108 - Residential      | В  | 67           | 61       | 65                | +4              | N            |  |
| R109 - Residential      | В  | 67           | 59       | 63                | +4              | N            |  |
| R110 - Residential      | В  | 67           | 67       | 68                | +1              | Υ            |  |
| R111 - Residential      | В  | 67           | 66       | 67                | +1              | Y            |  |
| R112 - Residential      | В  | 67           | 65       | 67                | +2              | Υ            |  |
| R113 - Residential      | В  | 67           | 60       | 63                | +3              | N            |  |
| R114- Residential       | В  | 67           | 61       | 65                | +4              | N            |  |



| TABLE 2: TRAFFIC NOISE LEVELS dB(A) Leq (Cont'd) |                 |              |          |                   |                 |              |
|--|-----------------|--------------|----------|-------------------|-----------------|--------------|
| Representative Receiver                          | NAC<br>Category | NAC<br>Level | Existing | Predicted<br>2035 | Change<br>(+/-) | Noise Impact |
| R115 - Residential                               | В               | 67           | 59       | 63                | +4              | N            |
| R116 - Residential                               | В               | 67           | 60       | 64                | +4              | N            |
| R117 - Residential                               | В               | 67           | 60       | 63                | +3              | N            |
| R118 - Residential                               | В               | 67           | 67       | 68                | +1              | Y            |
| R119 - Residential                               | В               | 67           | 59       | 62                | +3              | N            |
| R120 - Residential                               | В               | 67           | 58       | 60                | +2              | N            |
| R121 - Residential                               | В               | 67           | 69       | 69                | 0               | Y            |
| R122 - Residential                               | В               | 67           | 68       | 69                | +1              | Y            |
| R123 - Residential                               | В               | 67           | 66       | 67                | +1              | Y            |
| R124 - Residential                               | В               | 67           | 66       | 67                | +1              | Y            |
| R125 - Residential                               | В               | 67           | 68       | 68                | 0               | Y            |
| R126 - Residential                               | В               | 67           | 58       | 61                | +3              | N            |
| R127 - Residential                               | В               | 67           | 58       | 61                | +3              | N            |
| R128 - Residential                               | В               | 67           | 67       | 68                | +1              | Y            |
| R129 - Residential                               | В               | 67           | 67       | 68                | +1              | Υ            |
| R130 - Residential                               | В               | 67           | 64       | 65                | +1              | N            |
| R131 - Residential                               | В               | 67           | 60       | 64                | +4              | N            |
| R132 - Residential                               | В               | 67           | 63       | 65                | +2              | N            |
| R133 - Residential                               | В               | 67           | 65       | 67                | +2              | Υ            |
| R134 - Residential                               | В               | 67           | 67       | 68                | +1              | Υ            |
| R135 - Residential                               | В               | 67           | 66       | 67                | +1              | Υ            |
| R136 - Residential                               | В               | 67           | 65       | 66                | +1              | Υ            |
| R137 - Residential                               | В               | 67           | 65       | 66                | +1              | Υ            |
| R138 - Residential                               | В               | 67           | 62       | 65                | +3              | N            |
| R139 - Residential                               | В               | 67           | 65       | 67                | +2              | Υ            |
| R140 - Residential                               | В               | 67           | 57       | 59                | +2              | N            |
| R141 - Residential                               | В               | 67           | 59       | 61                | +2              | N            |
| R142 - Residential                               | В               | 67           | 58       | 61                | +3              | N            |
| R143 - Residential                               | В               | 67           | 67       | 68                | +1              | Υ            |
| R144 - Residential                               | В               | 67           | 58       | 60                | +2              | N            |
| R145 - Residential                               | В               | 67           | 62       | 65                | +3              | N            |
| R146 - Residential                               | В               | 67           | 60       | 63                | +3              | N            |
| R147 - Residential                               | В               | 67           | 61       | 64                | +3              | N            |
| R148 - Residential                               | В               | 67           | 62       | 65                | +3              | N            |
| R149 - Residential                               | В               | 67           | 61       | 64                | +3              | N            |
| R150 - Residential                               | В               | 67           | 61       | 64                | +3              | N            |
| R151 - Residential                               | В               | 67           | 67       | 66                | -1              | Υ            |
| R152 - Residential                               | В               | 67           | 61       | 63                | +2              | N            |

# **US-82 Traffic Noise Analysis**

| TABLE 2: TRAFFIC NOISE LEVELS dB(A) Leq (Cont'd) |                 |              |          |                   |                 |              |
|--|-----------------|--------------|----------|-------------------|-----------------|--------------|
| Representative Receiver                          | NAC<br>Category | NAC<br>Level | Existing | Predicted<br>2035 | Change<br>(+/-) | Noise Impact |
| R153 - Residential                               | В               | 67           | 64       | 66                | +2              | Y            |
| R154 - Church                                    | D               | 51           | 44       | 46                | +2              | N            |
| R155 - Driving School                            | D               | 51           | 41       | 44                | +3              | N            |
| R156 - Residential                               | В               | 67           | 65       | 68                | +3              | Υ            |
| R157 - Residential                               | В               | 67           | 64       | 67                | +3              | Y            |
| R158 - Residential                               | В               | 67           | 58       | 61                | +3              | N            |
| R159 - Residential                               | В               | 67           | 62       | 63                | +1              | N            |
| R160 - Residential                               | В               | 67           | 67       | 68                | +1              | Υ            |
| R161 - Residential                               | В               | 67           | 65       | 66                | +1              | Y            |

#### POTENTIAL NOISE ABATEMENT MEASURES

The 23 Code of Federal Regulations, Part 772 identifies certain noise abatement measures that may be considered in the project design to reduce traffic noise impacts. These abatement measures include: traffic management, alteration of alignments, buffer zones, building insulation, and the construction of sound barriers.

Before any abatement measure can be proposed for incorporation into the project, it must be both feasible and reasonable. In order to be "feasible," the abatement measure must be able to reduce the noise level at greater than 50% of impacted, first row receivers by at least five dB(A); and to be "reasonable," it must not exceed the cost-effectiveness criterion of \$25,000 for each receiver that would benefit by a reduction of at least five dB(A) and the abatement measure must be able to reduce the noise level at least one impacted, first row receiver by at least seven dB(A).

#### **Traffic Management**

Control devices could be used to reduce the speed of the traffic; however, the minor benefit of one dB(A) per five mph reduction in speed does not outweigh the associated increase in congestion and air pollution. Moreover, reduced speed limits will not likely be observed. Other measures such as time or use restrictions for certain vehicles are prohibited on state highways.

#### Alteration of Horizontal and/ or Vertical Alignments

The proposed US-82 alignment is shifted slightly toward the south. For the most part, traffic will be 4' in west bound passing lane situations and 10' in west bound non-passing lane situations further away from noise receivers on the north side of US-82. The predicted 2035 noise levels are based on this shifted alignment. Shifting vertical alignments can have a positive effect on noise levels; however, the terrain in the project area is relatively flat and will not likely result in a positive impact on noise levels.

#### **Buffer Zones**

On the north side of US-82, buffer zones are not possible since the impacted properties have been constructed adjacent to the right of way and there is no available land for use as a buffer. Moreover, the acquisition of undeveloped property to act as a buffer zone is designed to avoid rather than abate traffic noise impacts and, therefore, is not feasible.

## **Building Insulation**

Use of building insulation as a traffic abatement measure is limited to interior noise-sensitive receptor locations within public-use buildings, defined as NAC "D" in Table 1 on Page 2. No public-use buildings are predicted to be impacted by this project.

#### **Noise Barriers**

Construction of a noise barrier is the most commonly used noise abatement measure. The feasibility of a noise barrier is based on its effectiveness in reducing traffic noise levels as well as any adverse impacts to property access, drainage, topography, utilities, safety, and maintenance requirements. A barrier which reduces noise levels by a minimum of five dB(A) is considered effective.

Noise barriers were evaluated for each of the impacted receiver locations. Noise barriers would not be feasible and reasonable for any of the following impacted receivers and, therefore, are not proposed for



incorporation into the project:

R9-R12, R14-R15, R23-R24, R26-R31, R33-38, R40-R41, R43-R46, R48, R52-R54, R57-R61, R63-R68, R71-R72, R74, R77, R80, R83-R86, R88-R95, R98, R100-R103, R110-R112, R118, R121-R125, R128-R129, R133-R137, R139, R143, R151, R153, R156-R157, R160-R161: these receivers are separate individual residences with driveways that extend perpendicular from US-82 which makes the possibility of a barrier unfeasible.

R70 and R63: a noise barrier was investigated to mitigate the predicted traffic noise level impact to these two impacted residences. A wall 565' long and 10' high, shown in Exhibit 3.0, would provide up to 3 dB(A) reduction in noise level, which is less than minimum to be considered.

R106: a noise wall would be feasible based on the location of this single residence. However, a noise wall would not achieve the minimum noise reduction.

From the above analysis, noise barriers would not be feasible and reasonable for any of the impacted receivers in Table 2 and, therefore, are not proposed for incorporation into the project. The ineffective conceptual wall barrier design would also exceed the \$25,000 per receiver cost-effectiveness criterion.

#### CONSTRUCTION NOISE

The major construction elements of this project are expected to be bridge building, earth removal, hauling, grading, and paving. General construction noise impacts, such as temporary speech interference for passersby and those individuals living or working near the project, can be expected particularly from bridge construction, paving operations and grading equipment. Extremely loud construction noise activities such as the usage of impact hammers will provide sporadic, temporary, and potentially significant noise impacts in localized areas.

Whenever possible, measures should be taken to reduce the duration and intensity of construction noise impacts, such as work-hour limitations, enforcing equipment muffler and maintenance requirements, locating haul-road locations sensitive to neighboring land use, and the restriction of tailgate banging. In addition, the neighboring property owners and users should be provided with a means to register complaints about construction noise that includes timely response and follow-up procedures.

To reduce the potential for noise impacts at the majority of residential properties, work should not be allowed during typical sleeping hours and limited during weekends. Impact-type activities especially should be conducted in residential areas while people are at work and children are at school. Any construction activities that are necessary during evening and overnight hours should be closely coordinated so that appropriate mitigation strategies can be put into place before the construction activities are started.

There are three churches among the residential and commercial properties along this project located on the north side. One is located at the northwest corner of County Road 3204 intersection with US-82. Another is located approximately 1,600 feet east of County Road 3204. A third location is roughly 1,000 feet west of FM 3378. Evening and weekend work should be scheduled to be sensitive to not interrupting activities and services being conducted at the church property.



# **US-82 Traffic Noise Analysis**

There is also a school at the northeast corner of FM 2789 and US-82 intersection. Construction noise near the school should not be an issue; however, if possible, truck traffic should be routed away from the school during school hours.



#### COORDINATION WITH LOCAL OFFICIALS

The 23 CFR Part 772 delegates to highway agencies the responsibility for taking measures that are prudent and feasible to assure that the location and design of highways are compatible with base year and planned land uses.

To assist local authorities in exercising land use control over the undeveloped lands adjacent to the roadways proposed for this project, land use compatibility noise data was developed. Table 3 provides the typical distance at which the 66 dB(A) and 71 dB(A) noise levels occur. If no distance is provided, the contour is predicted to fall within the proposed right of way.

| TABLE 3: 66 AND 71 dB(A) CONTOURS FOR DESIGN YEAR 2035 |  |  |  |  |  |  |  |
|--|--|--|--|--|--|--|--|
| Segment  | Distance <sup>1</sup> to 66 dB(A) Contour (feet) | Distance <sup>1</sup> to 71 dB(A) Contour (feet) |  |  |  |  |  |
| West of FM 1840  | North = 155                                      | North =67  |  |  |  |  |  |
|  | South = ROW                                      | South = ROW                                      |  |  |  |  |  |
| East of FM 1840 to Co. Rd 4112                         | North = 170                                      | North = 77                                       |  |  |  |  |  |
|  | South = 200                                      | South = ROW                                      |  |  |  |  |  |
| 1,700' east of Co. Rd 4112 to Co.                      | North = 170                                      | North = 77                                       |  |  |  |  |  |
| Rd 4115  | South = 185                                      | South = Inside ROW                               |  |  |  |  |  |
| East of Co. Rd 4115 to FM 2789                         | North = 170                                      | North = 77                                       |  |  |  |  |  |
|  | South = 200                                      | South = Inside ROW                               |  |  |  |  |  |
| FM 2789 to Co. Rd 3104                                 | North = 170                                      | North = 80                                       |  |  |  |  |  |
|  | South = 210                                      | South = Inside ROW                               |  |  |  |  |  |
| Co. Rd 3104 to SH 98                                   | North = 170                                      | North = 80                                       |  |  |  |  |  |
|  | South = 210                                      | South =Inside ROW                                |  |  |  |  |  |
| US 98 to end of project                                | North = 180                                      | North = 80                                       |  |  |  |  |  |
|  | South = 220                                      | South = 122                                      |  |  |  |  |  |

<sup>&</sup>lt;sup>1</sup>Distances measured from existing roadway centerline

Although the information contained in Table 3 is based on the results of the noise modeling, it is not site-specific for any area along proposed US-82. Variations in terrain and the roadway profile can result in changes to the distances to these noise contours. This information is intended to provide a general guide for future planning, but should not be used in the final design or layout of future development.

A copy of this traffic noise analysis will be available to local officials. On the date of approval of this document (Date of Public Knowledge), FHWA and TxDOT are no longer responsible for providing noise abatement for new development adjacent to the project.


## **CONCLUSION**


This noise assessment for the US-82 Improvements (CSJ: 0046-04-057) was conducted according to the requirements of 23 CFR 772, the TxDOT Guidelines for Analysis and Abatement of Roadway Traffic Noise, March 1, 2011. Noise levels for noise-sensitive land uses along the proposed improvements were calculated using the FHWA's Traffic Noise Model, Version 2.5. Noise impacts were predicted to occur at 90 residential properties.

Noise abatement was considered at each impact. The findings of the abatement study concluded that traffic management, alignment alterations, buffer zones, building insulation, and noise barrier are not feasible abatement measures.



# **EXHIBITS**





# **EXHIBITS**

